

UNITED STATES

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE*
(Other instructions on reverse side)

Page 1 of 2 No. 1004-0136
Expires August 31, 1985

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL [X] DEEPEN [] PLUG BACK []
OIL WELL [] GAS WELL [X] OTHER [] SINGLE ZONE [] MULTIPLE ZONE []

b. TYPE OF WELL

OIL WELL [] GAS WELL [X] OTHER []

2. NAME OF OPERATOR

CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR

CNG Tower, 1450 Poydras Street, New Orleans, LA 70112-5000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

10 miles SW of Ouray

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. unit line if) 1,438'

16. NO. OF ACRES IN LEASE

400

17. NO. OF ACRES ASSIGNED
TO THIS WELL

160

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEA 2,860'

19. PROPOSED DEPTH

7,400'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5,101' GR

22. APPROX. DATE WORK WILL START

October, 1992

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24#	+/- 350	Cement to surface
7 7/8"	5 1/2"	17#	+/- 7,400	Cement calc to surface

1. Drill a 12 1/4" hole with an air rig to 350', run a 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 7,400' with a salt water mud system. No cores are planned. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, test, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
6. Primary zones of interest are the Wasatch, Chapita Wells & Ute land Buttes.
7. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
8. In the event circulation is lost, air or air assisted mud will be utilized.

FORMATION TOPS

DEPTHS

Wasatch 4,600'
Chapita Wells 5,250'
Ute land Buttes 6,350'

CNG Producing Company respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depth. Give blowout preventer program, if any.

24. SIGNED R. S. Linger
David L. Linger

TITLE Senior Drilling Engineer, GAS, AND MINING

DATE: 10/13/92

BY: J. H. Johnson

WELL SPACING: 649-2-3

(This space for Federal or State office use)

PERMIT NO. 43-047-30391 APPROVAL DATE

APPROVED BY

TITLE DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side


Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or claims.

CONFIDENTIAL

T10S, R20E, S.L.B. & M.

CNG PRODUCING COMPANY

WELL LOCATION, RBU #2-23F,
LOCATED AS SHOWN IN THE NW 1/4 NE 1/4
OF SECTION 23, T10S, R20E, S.L.B. & M,
UNITA COUNTY UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF.



TRI STATE LAND SURVEYING & CONSULTING
38 EAST 100 NORTH, VERNAL, UTAH 84078
(801) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: SS KH
DATE: 9/12/92	WEATHER: CLEAR & WARM
NOTES:	FILE # RBU #2-23F

X = SECTION CORNERS LOCATED
BASIS OF BEARINGS; G.L.O. PLAT 1911
BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (BIG PACK MOUNTAIN NW)

DRILLING PLAN
APPROVAL OF OPERATIONS

Attachment for Permit to Drill

Name of Operator: **CNG PRODUCING COMPANY**

Address: **CNG TOWER - 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000**

WELL LOCATION: Well No. 2-23F

Uintah, Utah

1. **GEOLOGIC SURFACE FORMATION**

Uintah

2. **ESTIMATE IMPORTANT GEOLOGIC MARKERS**

<u>Formation</u>	<u>Depth</u>
Wasatch Tongue	4000'
Green River Tongue	4350'
Wasatch	4600'
Chapita Wells	5250'
Uteland Buttes	6350'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS**

<u>Formation</u>	<u>Depth</u>	<u>Remarks</u>
Wasatch Tongue	4000'	Oil Zone
Chapita Wells	5250'	Gas Zone
Uteland Buttes	6350'	Gas Zone

CONFIDENTIAL

4. **PROPOSED CASING PROGRAM**

8-5/8", 24#/ft, H-40, 0'-400' - Cemented to Surface
5", 17#/ft, N-80 & K-55, 0'- 7400' - Cemented to Surface

5. **OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL**

BOP stack has a 3000 psi working pressure. BOP will be pressure tested to 3,000 psi before drilling casing cement plug. Pipe rams will be operated daily and blind rams as possible.

6. The well is to be drilled with a KCL mud system maintaining a weight of approximately 9#/gal.

7. AUXILIARY EQUIPMENT TO BE USED

1. Kelly Cock.
2. Full opening valve on floor with DP connection for use when Kelly is not in string.

8. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

A mud logger will be used from 3,000' to TD. Possible DST in Wasatch Tongue. The logging program will include Dual Lateral/GR log TD to Surface, Density/Neutron - TD - 3,500' possible dipmeter and rotary cores over selected intervals.

9. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

No normal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas. The anticipated bottom hole pressure is 2,610 PSI.

10. WATER SUPPLY

CONFIDENTIAL

- A. Water to be used for drilling will be hauled from West Hazmat Trucking's well located about 2 miles North of Oray Application #51641 User's Claim - Code #43, Serial #8290. Water will also be hauled from Dalbo Trucking's well in Oray, Application #53617 User's Claim - Code #43 Serial #5496.
- B. No pipelines are anticipated. Hauling will be on the road(s) shown in Attachment No. 3.
- C. No water well is anticipated to be drilled at this time.

11. CEMENT SYSTEMS

SURFACE

+/-224 sks 25:75 Poz G cement, 2% S-I CaCl₂, .25#/sk D-29 Flake

PRODUCTION

Lead Slurry - +/-195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite, .25#/sk D-29 Celloflake.

Tail Slurry - +/-335 sk RFC 10-0 (thixotropic).

12. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: October, 1992
Duration: 20 Days

SURFACE CASING CEMENT PROGRAM

Set 8 5/8" casing in 12 1/4" open hole cement to surface. Volume calculated using 75% excess.

SPACER:

Pump 20 BBLS lightly gelled water followed by 5 BBLS fresh H₂O ahead of cement to water wet the well bore after air drilling. Displace with fresh water.

CEMENT SYSTEM

± - 224 SK 25:75 Poz G "Tail-In" Cement, 2% S-1 CaCl₂, .25#/sk D-29 Celloflake.

Weight	15.40 lb/gal
Yield	1.11 ft ³ /sk
Water	4.71 gal/sk

Thickening Time at 118°

1:42min.

Compressive Strength at 80°

8 hrs. 750 psi
16 hrs. 1800 psi
24 hrs. 2400 psi

CONFIDENTIAL

CASING HARDWARE:

- 1 Cement Guide Shoe
- 1 Insert Float
- 3 Centralizers
- 1 Stop Ring
- 1 Thread Lock
- 1 Top Wood Plug

NOTE -

DS will at no charge (unless used), in addition to the casing cement, have 100 sk of cement, CaCl₂ for 2% by volume, and 80' to 100' of 1" tubing on location for top out job should cement not be returned to surface.

LONGSTRING CEMENT

Set 5 1/2" casing in a 7 7/8" open hole.
Lead cement slurry to fill from 750' above top pay zone to surface.
Tail cement slurry to fill from TD to 750' above the pay zone.
Both volumes are calculated using 15% excess.

SPACER:

(DAP Mud System) 20 BBL CW-100 (Sodium Silicate); 20 BBL Water
(KCL Mud System) 10 BBL water

Displace with 3% KCL water using .2% L-55 Clay Stabilizer in the first 50 bbl of displacement.

CEMENT SYSTEMS

Lead Slurry

± - 195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite, .25#/sk D-29 Celloflake.

Weight	10.80 lb/gal
Yield	3.91 ft ³ /sk
Water	24.40 gal/sk

Thickening Time at 180°	4hrs +
Compressive Strengths in 24 hrs.	375 psi
Fluid Loss	240 cc/30 min.

CONFIDENTIAL

Tail Slurry

± - 335 sk RFC 10-0 (thixotropic).

Weight	14.20 lb/gal
Yield	1.61 ft ³ /sk
Water	7.91 gal/sk

Thickening Time at 165 deg. BHCT	min.
Compressive Strength in 12 hrs.	845 psi
24 hrs.	1470 psi

Date NOS Received: _____

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: CNG PRODUCING COMPANY

Well Name & Number: RBU 2-23F

Lease Number: U-013793-A

Location: NW/4 of NE/4 Sec. 23 T. 10S R. 20E

Surface Ownership: Bureau of Land Management

NOTIFICATION REQUIREMENTS

- Location Construction - forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONFIDENTIAL

B. THIRTEEN POINT SURFACE USE PROGRAM:

Multipoint Requirement to Accompany APD

1. Existing Roads - describe the following and provide a legible map, labeled and showing:
 - a. Proposed wellsite as staked and access route to location, including distances from point where access route exists establish roads. (Actual staking should include tow directional reference stakes.)
 - b. Route and distance from nearest town or locatable reference point, such as a highway or county road, to where well access route leaves main road.
 - c. Access road(s) to location color-coded or labeled.
 - d. Plans for improvement and/or maintenance of existing roads. (Appropriate rights-of-way for off lease roads should be attached.)
2. Planned Access Roads--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:
 - a. Length - 2,100'
 - b. Width - 30 foot right-of-way with 18 foot running surface maximum.
 - c. Maximum grades - 8%
 - d. Turnouts - _____
 - e. Drainage design - Bar Pits
 - f. Location and size of culverts and/or bridges, and brief description of any major cuts and fills - _____
 - g. Surfacing material (source) - Native
 - h. Necessary gates, cattleguards, or fence cuts and/or modification to existing facilities - _____

CONFIDENTIAL

(New or reconstructed roads are to be centerline-flagged at time of location staking.)

All travel will be confined to existing access road rights-of-way.

Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

____ Right-of-Way Application needed.

Not needed

____ The operator/lessee or his/her successor shall be responsible for all maintenance on cattleguards or gates associated with this oil and/or gas operation.

3. Location of Existing Wells - describe the following and provide a map or plat of all wells within a 1 mile radius of the proposed well location showing and identifying existing:

- a. Water wells - None
- b. Abandoned wells - 15-23
- c. Temporarily abandoned wells - None
- d. Disposal wells - None
- e. Drilling wells - None
- f. Producing wells - RBU 10-22F, RBU 7-22F, RBU 5-14F, RBU 8-14F, 92D-13, 64-24, 65-25, 71-26
- g. Shut-in wells - None
- h. Injection wells - None

CONFIDENTIAL

4. Location of Existing and/or Proposed Facilities

a. On well pad: Show the following existing area facilities and dimensions to be utilized if the well is successfully completed for production (detail painting plans and color if applicable):

- (1) Tank batteries
- (2) Production facilities
- (3) Oil gathering lines
- (4) Gas gathering lines
- (5) Injection lines
- (6) Disposal lines
- (7) Surface pits (separate application per NTL-2B requirements)

(Indicate if any of the above lines are buried.)

b. Off well pad: Same as above. Off lease flowlines may require rights-of-way or special use permits, check with the District Office Realty Specialist. (Include a diagram of the proposed attendant lines, i.e., flowlines, powerlines, etc., if off well pad location.)

- (1) Proposed location and attendant lines shall be flagged off of well pad prior to archaeological clearance.
- (2) Dimensions of facilities
- (3) Construction methods and materials
- (4) Protective measures and devices to protect livestock and wildlife

Note: Operator has option of submitting information under 4A and B, after well is completed for production, by applying for approval of subsequent operations.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

Tank batteries will be placed on the North side

CONFIDENTIAL

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match on of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Desert Tan.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. Location and Type of Water Supply

- a. Show location and type of water supply, either by 1/4, 1/4 section on a map or by written description hailed from West Hazmat or Dalbo water wells
- b. State method of transporting water, and show any roads or pipelines needed.
- c. If water well is to be drilled on lease, so state. _____

*The operator will be responsible for acquiring the necessary permit to obtain water to be used for drilling activities.

6. Source of Construction Materials

- a. Show information either on map or by written description - _____
- b. Identify if from Federal or Indian (tribal or allotted) land.
- c. Describe where materials such as sand, gravel, stone, and soil material are to be obtained and used.

*If fill materials are needed to construct roads or well sites, proper permits must be obtained from the Surface Management Agency, unless materials are obtained from a private source.

*A mineral materials application (is/is not) required.

7. Methods of Handling Waste Disposal

- a. Describe methods and location of proposed safe containment and disposal of each type of waste material, including:
 - (1) Cuttings - bury in pit
 - (2) Sewage - haul to sewer lagoon
 - (3) Garbage (trash) and other waste material - haul to disposal
 - (4) Salts - not used
 - (5) Chemicals - non-toxic only; evaporate in pits
- b. Provide a plan for eventual disposal of drilling fluids and any produced oil or water recovered during testing operations. evaporate in pit - no oil anticipated

*Burning will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BLM administered lands:

The reserve pit shall be constructed so as not to leak, break, or allow discharge.

CONFIDENTIAL

The reserve pit (shall/shall not) be lined if necessary to conserve water.

"If a plastic nylon reinforced liner is used, it will be a minimum of 10 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O."

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

On BIA administered lands:

All reserve pits will be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit.)

CONFIDENTIAL

___ To protect the environment.

If the reserve pit is lined the operator will provide the BLM a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements described by Part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.

X To protect the environment (without a chemical analysis).

Reserve pits will be constructed so as not to leak, break, or allow discharge of liquids.

___ Storage tanks will be used if drill sites are located on tribal irrigable land, flood plains, or on lands under crop production.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. Ancillary Facilities

Camp facilities or airstrips will not be allowed unless otherwise approved.

9. Well Site Layout--provide a plat (not less than 1" = 50') showing:

- a. Cross-sections of proposed drill pad with approximate cuts and fills and the relation to topography.
- b. Location of mud tanks, reserve, and flare pits, pipe racks, living facilities, and soil material stockpiles, etc. (Approval as used in this section means field approval of location.)
- c. Rig orientation, parking area, and access roads, etc.

The reserve pit will be located on the : Southeast corner

The flare pit will be located downwind of the prevailing wind direction on the South

a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil (first four inches) will be stored on the: South corner

Access to the well pad will be from the: Southwest

CONFIDENTIAL

___ Diversion ditch(es) shall be constructed on the _____ side of the location (above / below) the cut slope, draining to the _____.

___ Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____.

___ The drainage(s) shall be diverted around the _____ side(s) of the well pad location.

___ The reserve pit and/or pad location shall be constructed _____.

___ The _____ corners of the well pad will be rounded off to avoid the _____.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a. 39-inch net wire shall be used with at least one strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).

- b. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times when pit is shrunk for production pit.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguard (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. Plans for Restoration of Surface

a. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 6 months from the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc., will be removed.

CONFIDENTIAL

Contact appropriate surface management agency for required seed mixture.

b. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

On BIA administered lands:

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) re-establishing irrigation systems where applicable, (b) re-establishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and, (c) ensuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.

11. Surface Ownership:

Access Road: Bureau of Land Management

Location: Bureau of Land Management

"If the access road and/or location involves private or state agency owned surface, a copy of the surface owners agreement is required prior to approval of the APD."

12. Other Additional Information

CONFIDENTIAL

- a. The Operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to :

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible to mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- b. The operator will control noxious weeds along right-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- c. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

On BIA administered land:

CONFIDENTIAL

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way Authorization". All operators, subcontractors, vendors and their employees or agents may not disturb salable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved rights-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uinta and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members, (d) that permits must be obtained from the BIA before cutting firewood or other timber products and (e) only authorized personnel permitted.

All well site locations on the Uinta and Ouray Indian Reservation will have an appropriate sign indicating the name of the operator, the lease serial number, the well name and number, the survey description of the well (either footages or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations

___ No construction or drilling activities shall be conducted between _____ and _____ because of _____

___ No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.

___ No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.

___ There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).

___ No cottonwood trees will be removed or damaged.

X A silt catchment dam and basin will be constructed according to BLM specifications approximately 250 ft. northwest of the location, where flagged and 1 silt catch dam and basin will be constructed on the access road 100' south of the junction to the road.

13. Lessee's or Operators Representative and Certification

Representative

Name: _____

Address: _____

Phone No: _____

CONFIDENTIAL

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by _____ CNG Producing Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

October 1, 1992
Date

R. S. Linger for David L. Linger
Senior Drilling Engineer
Name and Title

Onsite Date: September 29, 1992


CONFIDENTIAL

Participants on Joint Inspection


<u>Greg Darlington</u>	<u>Environmental Tech.</u>
<u>Jim Jackson</u>	<u>CNG Consultant</u>
<u>Carl Wright</u>	<u>BLM - Plant Scientist</u>
<u>Darwin Kulland</u>	<u>Manager - CNG Producing</u>
<u>Harry Barber</u>	<u>BLM - Wildlife</u>
<u>Harvey Jackson</u>	<u>Jackson Construction</u>
<u>Craig Obermuller</u>	<u>Craigs Roustabouts</u>
<u>Brent Stubbs</u>	<u>Stubbs Construction</u>

CNG PRODUCING COMPANY

WELL LAYOUT RBU 2-23F




SCALE: 1" = 50'




TRI-STATE LAND SURVEYING
P.O. BOX 533 VERNAL, UT. 84078
(801)781-2501

CNG PRODUCING COMPANY


MAP "A"







CNG PRODUCING COMPANY
MAP "B"

ONG PRODUCING COMPANY
WELL PLAT RBU #2-23-F



Amended after onsite 4/29/92 J.A.J.





CNG PRODUCING COMPANY
RIVER BEND UNIT
 UTAH COUNTY, UTAH
1992 PLAN OF DEVELOPMENT
PARTICIPATING AREAS LAND PLAT
 ZG2LC300,26JRBU8XIPD.DGN

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Utah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent☐ Abandonment☐ Change of Plans☒ Subsequent Report☐ Recompletion☐ New Construction☐ Final Abandonment Notice☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut-Off☐ Altering Casing☐ Conversion to Injection☒ Other - Variance
in casing☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Under Onshore Order #2, casing and cementing requirements, it states "All casing, except the conductor casing, shall be new or reconditioned and tested used casing that meets or exceeds API standards for new casing" the 8 5/8" 24# H-40 surface casing designed for this well and other wells in the River Bend Unit meets all of the above criteria for the order. The 8 5/8" casing is a limited service pipe which means it does not meet API standards. However, the pipe is new and was Hydro statically tested to 2,700 PSI which equals API standards for 8 5/8" 24# K-55 casing.

We respectfully submit this sundry and attached letter from the company the pipe was purchased from

If any additional information is needed, please advise.

CONFIDENTIAL

14. I hereby certify that the forgoing is true and correct

Signed R. S. Linger for Title Senior Drilling Engineer Date October 1, 1992
David L. Linger

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:


Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

SELF-CERTIFICATION STATEMENT

Self-certification statement. Under the Federal regulation in effect as of June 15, 1988 designation of operator forms are no longer required when the operator is not the 100% record title holder. An operator is now required to submit a self-certification statement to the appropriate Bureau office stating that said operator has the right to operate upon the leasehold premises. Said notification may be in the following format:


"Please be advised that CNG Producing Company is considered to be the operator of Well No. 2-23F NW 1/4 of NE 1/4 Section 23, Township 10, Range 20; Lease U-013793-A; Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by American Casualty Company of Reading, PA, Bond #524 7050.



R. S. Gloger
Drilling Manager


CONFIDENTIAL

BOP STACK



CONFIDENTIAL

CHOKER MANIFOLD



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

DATE RECEIVED: 10/05/92

OPERATOR: CNG PRODUCING COMPANY
WELL NAME: RBU 2-23F

OPERATOR ACCT NO: N-0005

API NO. ASSIGNED: 43-047-30391

LEASE TYPE: FED LEASE NO: J-013793-A
LOCATION: NWNE 23 - T10S - R20E UINTAH COUNTY
FIELD: NATURAL BUTTES FIELD CODE: 630

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond
☒ (Number 1000)
☒ Potash (Y/N) N
☒ Oil shale (Y/N) N
☒ Water permit
☒ (Number West Hazmat)
☒ RDCC Review (Y/N) N
☐ (Date: _____)

LOCATION AND SITING:

☒ R649-2-3. Unit: Ruler Bend
☐ R649-3-2. General.
☐ R649-3-3. Exception.
☐ Drilling Unit.
☐ Board Cause no: _____
☐ Date: _____

COMMENTS: Included in 90 PDD approved 4-10-90

Oil shale area

STIPULATIONS: _____

CONFIDENTIAL
PERIOD
EXPIRED
ON 4-30-94



Norman H. Bangertter
Governor
Dee C. Hansen
Executive Director
Dianne R. Nielson, Ph.D.
Division Director

State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

October 13, 1992

CNG Producing Company
CNG Tower, 1450 Poydras Street
New Orleans, Louisiana 70112-6000

Gentlemen:

Re: RBU 2-23F Well, 982 feet from the north line, 1438 feet from the east line, NW 1/4 NE 1/4, Section 23, Township 10 South, Range 20 East, Uintah County, Utah

Pursuant to Utah Code Ann. § 40-6-18, (1953, as amended), Utah Admin. R. 649-2-3, Application of Rules to Unit Agreements and R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-Back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
2. Notification within 24 hours after drilling operations commence.
3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
4. Submittal of the Report of Water Encountered During Drilling, Form 7.
5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.

Page 2
CNG Producing Company
RBU 2-23F Well
October 13, 1992

6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Trash and sanitary waste should be properly contained and transported to approved disposal locations, not retained in or disposed of in pits on location or downhole. Prior to the commencement of drilling operations, the operator should consult the local/county sanitarian and/or the Department of Environmental Quality, Division of Drinking Water/Sanitation, regarding appropriate disposal of sanitary waste.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-047-32391.

Sincerely,



R.J. Fifth
Associate Director, Oil and Gas

Idc
Enclosures
cc: Bureau of Land Management
J.L. Thompson
WO11

**CNG Producing
Company**

A **CNG** COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

November 6, 1992

RECEIVED

NOV 09 1992

**DIVISION OF
OIL GAS & MINING**

Mr. Ed Forsman
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: River Bend Unit
RBU 2-23F Sec. 23-T10S-R20E

Dear Ed:

Per your request, enclosed please find the original and two copies of Form 3160-3 of the Application for Permit to Drill for the above referenced well. This form is being refiled since the location has been restaked. Also attached to the application is the revised survey plat.

CNG Producing Company is requesting all information be held confidential.

It would be appreciated if this permit could be expedited since drilling is planned to begin in November, 1992.

If you have any questions or need any further information, please feel free to contact me at (504) 593-7260 or our project engineer, David Linger, at (504) 593-7779. Thank you for your continued cooperation.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

cc: Tanny Searing - Utah Board of Oil, Gas & Mining

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

5. LEASE DESIGNATION AND SERIAL NO.
U-013793-A

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL [X] DEEPEN [] PLUG BACK []

b. TYPE OF WELL

OIL WELL [] GAS WELL [X] OTHER [] SINGLE ZONE [] MULTIPLE ZONE []

2. NAME OF OPERATOR

CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR

CNG Tower, 1450 Poydras Street, New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*

At surface 808' FNL & 2,286' FEL of Sec. 23-T10S-R20E

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

10 miles SW of Ouray

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. unit line if) 2,285'

16. NO. OF ACRES IN LEASE

400

17. NO. OF ACRES ASSIGNED
TO THIS WELL

160

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEA 2,699'

19. PROPOSED DEPTH

7,400'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5,101' GR

22. APPROX. DATE WORK WILL START

November, 1992

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24#	+/- 350	Cement to surface
7 7/8"	5 1/2"	17#	+/- 7,400	Cement oab to surface

1. Drill a 12 1/4" hole with an air rig to 350', run a 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 7,400' with a salt water mud system. No cores are planned. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, test, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
6. Primary zones of interest are the Wasatch, Chapita Wells & Ute land Buttes.
7. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
8. In the event circulation is lost, air or air assisted mud will be utilized.

FORMATION TOPS

DEPTHS

Wasatch 4,600'
Chapita Wells 5,250'
Ute land Buttes 6,350'

RECEIVED
DIVISION OF UTAH
OIL, GAS, AND MINING

NOV 0 9 1992

DATE: 11-12-92

BY: J. Matthew

DIVISION OF

OIL, GAS & MINING

CNG Producing Company respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depth. Give blowout preventer program, if any.

24. SIGNED David L. Linger
David L. Linger

TITLE Senior Drilling Engineer DATE 11/06/92

(This space for Federal or State office use)

PERMIT NO. 43-047-30391 APPROVAL DATE

APPROVED BY

TITLE DATE


CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side


T10S, R20E, S.L.B. & M.

CNG PRODUCING COMPANY

WELL LOCATION, RBU #2-23F.
LOCATED AS SHOWN IN THE NW 1/4 NE 1/4
OF SECTION 23, T10S, R20E, S.L.B. & M,
UNITA COUNTY UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE TO THE BEST OF
MY KNOWLEDGE AND BELIEF.



TRI STATE LAND SURVEYING CONSULTING
38 EAST 100 NORTH, VERNAL, UTAH 84078
(801) 781-2501

X = SECTION CORNERS LOCATED
BASIS OF BEARINGS; G.L.O. PLAT 1911
BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (BIG PACK MOUNTAIN NW)

SCALE: 1" = 1000'	SURVEYED BY: GS RM
DATE: 10/15/92	WEATHER: CLEAR & WARM
NOTES: ALTERNATE LOCATION	FILE # RBU #2-23F

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK			5. LEASE DESIGNATION AND SERIAL NO. U-013793-A	
1a. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>			6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
b. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/> SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>			7. UNIT AGREEMENT NAME	
2. NAME OF OPERATOR CNG PRODUCING COMPANY			8. FARM OR LEASE NAME RBU	
3. ADDRESS OF OPERATOR CNG Tower, 1450 Poydras Street, New Orleans, LA 70112-6000			9. WELL NO. 2-23F	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface 808' FNL & 2,286' FEL of Sec. 23-T10S-R20E At proposed prod. zone 43-047-32391			10. FIELD AND POOL, OR WILDCAT Island	
11. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* 10 miles SW of Ouray			12. COUNTY OR PARISH Utah	
13. STATE Utah			14. COUNTY OR PARISH Utah	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line if 2,285')		16. NO. OF ACRES IN LEASE 400	17. NO. OF ACRES ASSIGNED TO THIS WELL 160	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE 2,699'		19. PROPOSED DEPTH 7,400'	20. ROTARY OR CABLE TOOLS Rotary	
21. ELEVATIONS (Show whether DF, RT, GR, etc.) 5,101' GR			22. APPROX. DATE WORK WILL START November, 1992	

23. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24#	+/- 350	Cement to surface
7 7/8"	5 1/2"	17#	+/- 7,400	Cement only to surface

1. Drill a 12 1/4" hole with an air rig to 350', run a 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 7,400' with a salt water mud system. No cores are planned. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, test, and logs. Casing NOV 24 1992
6. program may be modified to provide added burst strength if needed for frac program.
7. Primary zones of interest are the Wasatch, Chapita Wells & Ute land Buttes.
8. All zones indicating potential for economically recoverable reserves will be tested in a normal OIL GAS & MINING
9. prudent manner.
10. In the event circulation is lost, air or air assisted mud will be utilized.

FORMATION TOPS	DEPTHS
Wasatch	4,600'
Chapita Wells	5,250'
Ute land Buttes	6,350'

RECEIVED

NOV 09 1992

CNG Producing Company respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depth. Give blowout preventer program, if any.

24. SIGNED David L. Linger TITLE Senior Drilling Engineer DATE 11/06/92

(This space for Federal or State office use)
PERMIT NO. APPROVAL DATE
APPROVED BY TITLE ASSISTANT DISTRICT MANAGER MINERALS DATE NOV 19 1992
CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

See Instructions On Reverse Side

CONDITIONS OF APPROVAL ATTACHED TO OPERATOR'S COPY

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

WELL LOCATION INFORMATION

Company/Operator: CNG PRODUCING COMPANY
API Number 43-047-32391
Well Name & Number: RBU 2-23F
Lease Number: U-013793A
Location: NWNE Sec. 23 T. 10S R. 20E
Surface Ownership: BLM
Date NOS Received 9/23/92
Date APD Received 10/5/92

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Company CNG Producing Company Well No. RBU 2-23F
Location NWNE, Section 23, T10S, R20E Lease No. U - 01470 - A

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of onshore Oil and Gas Order No. 2 for a 3M system for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at \pm 1,655. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to \pm 1,455 ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka	(801) 781-1190
Petroleum Engineer	

Ed Forsman	(801) 789-7077
Petroleum Engineer	

BLM FAX Machine	(801) 789-3634
-----------------	----------------

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

ENTITY ACTION FORM - FORM 6

ADDRESS CNG Tower

1450 Poydras Street

New Orleans, LA 70112-6000

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	07050	43-047-32391	RBU 2-23F	NW NE	23	10S	20E	Uintah	12/08/92	
WELL 1 COMMENTS: This well is located within River Bend Unit on BLM land. Entity added 12-14-92. <i>ja</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS											

ACTION CODES (See instruction on back of form)

- A - establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Susan M. Helbert
Signature

Regulatory Reports Assistant II
Title

December 8, 1992
Date

Phone No. (504) 593-7260

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

BUDGET BUREAU NO. 1004-0135

EFFECTIVE DATE: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT TO DRILL" for such proposals.

SUBMIT IN TRIPLICATE

RECEIVED

DEC 16 1992

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32391
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T105-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Spud Notice	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

This is to notify you that the RBU 2-23F was spudded by Top Hole Drilling on December 11, 1992.

They drilled 397' of 12 1/4" hole and ran 9 jts of 8 5/8" 23# H-40 casing and set at 389.39'.

Cemented by Dowell with 224 sks Class "G" Poz. Displace 8 5/8" casing with 21 bbls of fresh water. Plug was not bumped. Top of cement at 330'. Circulate 5 bbls of good cement to surface.

14. I hereby certify that the forgoing is true and correct

Signed David L. Linger Title Senior Drilling Engineer Date December 18, 1992

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

IF APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator
CNG PRODUCING COMPANY

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-5000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface - 982' FNL & 1,438' FEL of Sec. 23-T105-R20E

5. Lease Designation and Serial No.
U-01470-A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation
RBU

8. Well Name and No.
2-23F

9. API Well No.
43-047-32391

10. Field and Pool, or Exploratory Area
Island

11. County or Parish, State
Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other - Spud Notice

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water
(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

December 18 - December 23, 1992

Rig up rig. Nipple up BOPs. Test BOPs, kelly valve, dart valve, TIW, choke line, kill line and manifold to 1500 PSI. Test casing and hydril to 1500 PSI. Function test BOPs. Pick up bit, mud motor, shock sub & trip in hole. Tag cement at 306'. Drill cement, float and shoe. Install rotating head rubber. Drilling. Survey at 980'. Drilling. Survey at 1,579'. Drilling. Survey - line parted. Trip for tool. Drilling. Survey at 2,765'. Drilling. Survey at 3,352'. Drilling. Survey at 3,881'. Drilling. Survey at 4,511'. Drilling. Pull out of hole. Lay down mud motor and short sub. Rig service. Pick up 3 drill collars. Trip in hole. Circulate out gas. Wash to bottom. 30' fill. Drilling. Survey. Drilling. Survey at 5,943'. Drilling. TD at 6,120'. Mud wt. 8.9 PPG.

14. I hereby certify that the foregoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II

Date December 23, 1992

Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

1. Well name and number: RBU 2-23F
 API number: 43-047-32391
2. Well location: QQ NW NE section 23 township 10S range 20E county Uintah
3. Well operator: CNG Producing Company
 Address: CNG Tower - 1450 Poydras Street phone: (504) 593-7000
New Orleans, LA 70112-6000
4. Drilling contractor: Grace Drilling Company
 Address: 2801 Youngfield Street phone: (303) 234-1444
Suite 178 - Applewood Tech Center
Golden, CO 80401

5. Water encountered (continue on reverse side if necessary)

Depth		Volume (flow rate or head)	Quality (fresh or salty)
from	to		
2,265'	2,295'	50 BPH	Fresh

6. Formation tops: Wasatch Tongue 4,000'
- _____
- _____
- _____
- _____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I certify that this report is true and complete to the best of my knowledge.

Name David L. Linger
 Title Senior Drilling Engineer

Signature *David L. Linger*
 Date December 21, 1992

DEC 28 1992
 DIVISION OF
 OIL GAS & MINING

Comments:

This water flow was encountered while drilling with 294 GPM pump rate and 600 CFM air rate. The approximate fluid weight at the time this water flow was encountered is equal to a 4.5 PPG mud weight equivalent.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMITS TO DRILL" for such proposals.

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	JAN 04 1993	5. Lease Designation and Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY	DIVISION OF	6. If Indian, Allottee or Tribe Name
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	OIL GAS & MINING	7. If Unit or CA, Agreement Designation RBU
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E		8. Well Name and No. 2-23F
		9. API Well No. 43-047-32391
		10. Field and Pool, or Exploratory Area Island
		11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent☐ Abandonment☐ Change of Plans☒ Subsequent Report☐ Recompletion☐ New Construction☐ Final Abandonment Notice☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut-Off☐ Altering Casing☐ Conversion to Injection☒ Other - Spud Notice☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

December 24 - December 31, 1992

Drilling. Rig service. Drilling. Repair pump. Drilling. Survey at 6,449'. Drilling. Circulate and condition. Short trip 10 stands. Circulate and condition. Trip out of hole - chain out. Rig up Halliburton. Trip in hole. Loggers TD 6,897'. Log with Halliburton. Run CDL/DSN/DLL/GR. Trip in hole to 6,860'. Lay down drill pipe. Well flowing 2" stream. Run 159 jts 5 1/2" casing. Wash 6,836-6,876'. Circulate out gas. Cement casing with 440 sks HiLift, 3% D-44, .8% D-20, 10#/sk D-42, .25#/sk D-29, 1% D-79, .7% D-112, .2% D-46 followed by 650 sks 10-0 RFC. Displaced with 2% KCL with L-55. Bumped plug with 2000 PSI. Floats held OK. Set slips with 100,000#. Nipple down and cut off casing. Clean pits. Released rig on 12/26/92.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date December 31, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

PROJECT BUREAU NO. 1004-0135

EXPIRES: MARCH 31, 1993

5. Lease Designation and Serial No.

U-01470-A

6. If Indian, Allottee or Tribe Name

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

CNG PRODUCING COMPANY

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Surface - 982' FNL & 1,498' FEL of Sec. 23-T10S-R20E

808'

2286'

7. If Unit or CA, Agreement Designation
RBU

8. Well Name and No.

2-23F

9. API Well No.

43-047-32391

10. Field and Pool, or Exploratory Area
Island

11. County or Parish, State

Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent☒ Subsequent Report☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment☐ Recompletion☐ Plugging Back☐ Casing Repair☐ Altering Casing☒ Other - *Solid Notice*☐ Change of Plans☐ New Construction☐ Non-Routine Fracturing☐ Water Shut-Off☐ Conversion to Injection☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

January 9 - January 15, 1993

Rig up Halliburton and run GR/CCL from 6,953' to 4,500'. Tag up at 6,763'. Run in hole with 4" casing gun loaded with 2 SPF and perforate Zone #1 (6,262-70' & 6,616-26'). Pick up and run in hole with mule shoe collar, 1 jt, seating nipple and 193 jts. Nipple down BOP. Hang off tubing with end of tubing at 6,153', seating nipple at 6,120'. Nipple up tree. Rig down rig. Rig up Halliburton. Triple entry. Establish injection rate with 35 bbls of 2% KCL water. Zone broke at 2417 PSI. Treated Zone #1 (6,262-70' & 6,616-26') with 120,600 lbs of 20/40 frac sand and 1,099 bbls of fluid. Average treating pressure - 3650 PSI. Open tubing to pit on 24/64 choke.

14. I hereby certify that the forgoing is true and correct

Signed Susan HebertTitle Regulatory Reports Asst. IIDate January 15, 1993

Susan M. Hebert

(This space for Federal or State office use)

Approved by _____

Title _____

Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any agency of the United States any false, fictitious or fraudulent statements or representations as to a matter within its jurisdiction.

*See Instructions on Reverse Side

JAN 19 1993

DIVISION OF
OIL & GAS MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

RECEIVED

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-5000	9. API Well No. 43-047-32391
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent

☐ Abandonment

☐ Change of Plans

☐ Recompletion

☐ New Construction

☒ Subsequent Report

☐ Plugging Back

☐ Non-Routine Fracturing

☐ Casing Repair

☐ Water Shut-Off

☐ Final Abandonment Notice

☐ Altering Casing

☐ Conversion to Injection

☒ Other - Weekly Report

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

January 16 - January 22, 1993

Flowing tubing to pit on 24/64 choke returning 1/2" stream of water with 100 PSI on casing. Flow testing well with 10 PSI on tubing and 0 PSI on casing flowing on 24/64 choke. Returning 1/4" stream of water. Casing on a vacuum. Flowing well with 225 PSI on tubing and 250 PSI on casing flowing on 25/64 choke. Light mist will burn. Flowing well with 225 PSI on tubing and casing on 24/64 choke. Well will burn. Cleaned up good. Change choke from 24/64 to 18/64. Well flowing on 18/64 choke with 350 PSI on tubing and 500 PSI on casing. Well cleaned up good. Will burn.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date January 22, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
DGET BUREAU NO. 1004-0135
PIRES: MARCH 21, 1992

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32391
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E 808' 2286'	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

January 23 - January 29, 1993

Rig up rig. Well had 2100 PSI on casing & tubing. Bled pressure down to 700 PSI. Control well with 150 bbls of 2% KCL water. Nipple down tree. Nipple up BOP. Run in hole with 4 jts and set at 6,557'. No sand. Lay down 24 jts. Pull out of hole with 2 3/8" tubing. Rig up Halliburton. Run in hole and set 5 1/2" bridge plug at 6,190'. Pull out of hole. Pressure test bridge plug to 3000 PSI. Run in hole with 4" casing gun loaded with 2 SPF. Perforate Zone #2 (5,970-80' & 6,076-84'). No pressure increase. Run in hole with mule shoe collar, 1 jt, seating nipple & 184 jts. Land tubing with hanger and blast joint. Seating nipple set at 5,834' and end of tubing at 5,867'. Nipple down BOP. Nipple up tree. Rig down rig and equipment.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date January 29, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

FEB 01 1993

DIVISION OF
OIL GAS & MINERAL

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
DGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993
5. Lease Designation and Serial No.
U-01470-A

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT TO DRILL AND REENTRY TO A DIFFERENT RESERVOIR."

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other FEB 06 1993
2. Name of Operator
CNG PRODUCING COMPANY DIVISION OF
3. Address and Telephone No.
CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000 OIL GAS & MINING
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E
808' 2286'
7. If Unit or CA, Agreement Designation
RBU
8. Well Name and No.
2-23F
9. API Well No.
43-047-32391
10. Field and Pool, or Exploratory Area
Island
11. County or Parish, State
Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

- | | | |
|---|---|---|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Abandonment | <input type="checkbox"/> Change of Plans |
| | <input type="checkbox"/> Recompletion | <input type="checkbox"/> New Construction |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Plugging Back | <input type="checkbox"/> Non-Routine Fracturing |
| | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Altering Casing | <input type="checkbox"/> Conversion to Injection |
| | <input checked="" type="checkbox"/> Other - Weekly Report | <input type="checkbox"/> Dispose Water |
| | | (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) |

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

February 1 - February 5, 1993

Rig up triple entry. Establish injection rate. Zone broke at 4200 PSI. Pump injection test at 30 BPM and 4200 PSI. Treated Zone #2 (5,970-80' & 6,076-84') with 1,425 bbls of fluid and 150,200 lbs of 20/40 frac sand. Open tubing to pit on 24/64 choke. Flowing tubing to pit on 24/64 choke with 425 PSI on tubing and 275 PSI on casing returning gas at the rate of 1,564 MCF/D. Will burn. Left well flowing. Flowing tubing to pit on 24/64 choke with 350 PSI on tubing returning gas at the rate of 1,288 MCF/D, will burn dry. Install 18/64 choke. Open tubing to pit. Flowing tubing to pit on 18/64 choke with 450 PSI on tubing. Returning dry gas at the rate of 932 MCF/D, will burn.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date February 5, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

PROJECT BUREAU NO. 1004-0135

DUE DATE: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32391
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E 208' 2826'	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

February 6 - February 12, 1993

Repair flowline. Bled pressure down to 1000 PSI. Control well with 140 bbls 2% KCL water. Nipple down tree. Nipple up BOP. Pull out of hole with 185 jts. Well had 0 PSI. Rig up Halliburton wireline truck. Run in hole with bridge plug set at 5,700'. Pull out of hole. Pressure test to 3000 PSI. Tested OK. Run in hole with 185 jts. loaded with 2 SPF. Perforate Zone #3 (5,634-52'). Rig down wireline truck. Run in hole with 185 jts. 1 jt, seating nipple, 174 jts, blast jt and hanger. Set tubing with seating nipple at 5,518'. Tubing at 5,551'. Nipple down BOP. Rig up tree. Rig down rig.

RECEIVED

FEB 16 1993

DIVISION OF
OIL, GAS & MINING

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date February 12, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

GET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or extend into a different reservoir. Use "APPLICATION FOR PERMIT TO DRILL" for such proposals.

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	FEB 22 1993	5. Lease Designation and Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY	DIVISION OF	6. If Indian, Allottee or Tribe Name
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	OIL, GAS & MINING	7. If Unit or CA, Agreement Designation RBU
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E Amended - 208' FNL 2086' FEL		8. Well Name and No. 2-23F
		9. API Well No. 43-047-32391
		10. Field and Pool, or Exploratory Area Island
		11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent☐ Abandonment☐ Change of Plans☐ Recompletion☐ New Construction☒ Subsequent Report☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut-Off☐ Final Abandonment Notice☐ Altering Casing☐ Conversion to Injection☒ Other - Weekly Report☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

February 13 - February 19, 1993

Rig up Halliburton triple entry. Broke well down with 2,000 bbls of PAD. Treated Zone #3 (5,634-52') with 45,750 gallons of fluid and 121,400 lbs of 20/40 frac sand. Average treating pressure = 3300 PSI. Open tubing to pit on 24/64 choke. Flowing tubing to pit on 24/64 choke with 825 PSI on tubing and 975 PSI on casing returning gas at the rate of 3,037 MCF/D, will burn. Left tubing flowing.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date February 19, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

**CNG Producing
Company**

A **CNG** COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

February 24, 1993

Mr. David Little
District Manager
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RECEIVED

FEB 26 1993

**DIVISION OF
OIL GAS & MINING**

RE: Application for Disposal of Produced Water NTL-2B

Dear Mr. Little:

Pursuant to NTL-2B Revised August 1, 1978, CNG Producing Company hereby makes applications under Section 1, Exception No. 4. This request is for a 30' x 30' pit adjacent to gas separator in which production water is collected. The wells make less than five (5) bbls per day. The evaporation rate for the area is four (4) feet per year and the percolation rate of the soil is approximately 1" per day.

Some of the pits are unlined, (except with native clay), when they are not located next to drainage. These pits have also been tested for water loss. The pits that showed water loss are lined with native clay and a .12 mil liner.

<u>Well Name</u>	<u>Lease Number</u>	<u>Well Location</u>	<u>Section, Township & Range</u>
1. RBU 10-2F	ML-10716	NW SE	2-T10S-R20E
2. RBU 3-3E	U-013765	NE NW	3-T10S-R19E
3. RBU 5-3E	U-03505	SW NW	3-T10S-R19E
4. RBU 9-3E	U-035316	NE SE	3-T10S-R19E
5. RBU 3-10EX	U-035316	NE NW	10-T10S-R19E
6. RBU 5-10F	U-7206	SW NW	10-T10S-R20E
7. RBU 7-10E	U-13792	SW NE	10-T10S-R19E
8. RBU 9-10F	U-7206	NE SE	10-T10S-R20E
9. RBU 13-10F	BIA 14-20-H62-2645	SW SW	10-T10S-R20E
10. RBU 2-11F	U-01790	NW NE	11-T10S-R20E
11. RBU 3-11F	U-7206	NE NW	11-T10S-R20E
12. RBU 7-14E	U-013792	SW NE	14-T10S-R19E
13. RBU 9-14F	U-013793-A	NE SE	14-T10S-R20E
14. RBU 11-14F	U-013793-A	NE SW	14-T10S-R20E
15. RBU 13-14F	U-013793	SW SW	14-T10S-R20E
16. RBU 15-14E	U-013792	SW SE	14-T10S-R19E
17. RBU 15-14F	U-013793-A	SW SE	14-T10S-R20E
18. RBU 15-15E	U-013766	SW SE	15-T10S-R19E
19. RBU 3-16F	ML-3393-A	NE NW	16-T10S-R20E
20. RBU 7-16E	ML-13214	SW NE	16-T10S-R19E
21. RBU 13-16E	ML-13214	SW SW	16-T10S-R19E
22. RBU 15-16E	ML-13214	SW SE	16-T10S-R19E
23. RBU 5-17F	U-013769-C	SW NW	17-T10S-R20E
24. RBU 7-17F	U-013769-C	SW NE	17-T10S-R20E
25. RBU 9-17E	U-013766	NE SE	17-T10S-R19E
26. RBU 9-17F	U-013769-C	NE SE	17-T10S-R20E
27. RBU 13-17F	U-013769-C	SW SW	17-T10S-R20E
28. RBU 3-19FX	U-013769-A	NE NW	19-T10S-R20E
29. RBU 5-19F	U-013769-A	SW NW	19-T10S-R20E
30. RBU 3-20F	U-013793-A	NE NW	20-T10S-R20E

Mr. David Little, District Manager
Bureau of Land Management

Page 2
February 24, 1993

<u>Well Name</u>	<u>Lease Number</u>	<u>Well location</u>	<u>Section, Township & Range</u>
31. RBU 15-20F	U-0143520-A	SW SE	20-T10S-R20E
32. RBU 3-21F	U-013793-A	NE NW	21-T10S-R20E
33. RBU 7-21E	U-013766	SW NE	21-T10S-R19E
34. RBU 9-21F	U-014520-A	NE SE	21-T10S-R20E
35. RBU 11-21F	U-0143520-A	NE SW	21-T10S-R20E
36. RBU 13-21F	U-01435	SW SW	21-T10S-R20E
37. RBU 15-21F	U-0143520-A	SW SE	21-T10S-R20E
38. RBU 13-22E	U-013792	SW SW	22-T10S-R19E
39. RBU 14-22F	U-0143519	SE SW	22-T10S-R20E
40. RBU 15-22E	U-013792	SW SE	22-T10S-R19E
41. RBU 2-23F	U-013793-A	NW NE	23-T10S-R20E
42. RBU 4-23F	U-013793-A	NW NE	23-T10S-R20E
43. RBU 5-23E	U-013766	SW NW	23-T10S-R20E
44. RBU 9-24E	U-013794	NE SE	24-T10S-R19E
45. RBU 11-35B	U-017713	NE SW	35-T9S-R19E

43-047-32391

Exact location of the pits have been submitted with the site security diagram. All wells are located within the River Bend Unit except for RBU 9-17E, RBU 7-21E, RBU 13-22E, RBU 15-22E, and RBU 11-35B which are located outside the unit.

If you have any questions or need any further information, please feel free to contact either myself at (504) 593-7260 or our project engineer, Scot Childress, at (504) 593-7574. Thank you for your cooperation.

Sincerely,

Susan M. Hebert
Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: ✓ Utah Board of Oil, Gas & Mining
Yvonne Abadie
Scot Childress
Brian Coffin
Darwin Kulland
Jim Nicas
RBU Well files

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
BUDGET BUREAU NO. 1004-0158

RES: MARCH 31, 1993

8. Lease Designation and Serial No.

U-01470-A

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

CNG PRODUCING COMPANY

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-8000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Surface - 982' FNL & 17438' FEL of Sec. 23-T10S-R20E

908'

928'

7. If Unit or CA, Agreement Designation

RBU

8. Well Name and No.

2-23F

9. API Well No.

43-047-32391

10. Field and Pool, or Exploratory Area

Island

11. County or Parish, State

Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent☒ Subsequent Report☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment☐ Recompletion☐ Plugging Back☐ Casing Repair☐ Altering Casing☒ Other - Weekly Report☐ Change of Plans☐ New Construction☐ Non-Routine Fracturing☐ Water Shut-Off☐ Conversion to Injection☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

March 27 - April 2, 1993

Blad pressure down to 1000 PSI. Control well with 170 bbls 2% KCL water. Nipple down tree. Nipple up BOP. Pull out of hole with 2 3/8" tubing. Lay down 1 jt. Pull out of hole with 174 jts. Run in hole with bridge plug, 1 jt, seating nipple, 174 jts. Rig up drilling head. Pick up 3 jts, tag sand at 5,645'. Clean out sand from 5,645-5,700'. Circulate clean. Release bridge plug. Pull out of hole with 40 jts. Well started flowing gas to surface. Install 24/64 choke. Left well flowing. Pumped 150 bbls 2% KCL water to control well. Pull out of hole with 14 jts tubing. Laid down bridge plug. Run in hole with bridge plug retrieving head, pup jt, and 177 jts 2 3/8" tubing. Rig up drilling head. Pick up 12 jts tubing. Tagged sand at 6,107'. Broke circulation. Cleaned out sand from 6,102 to bridge plug at 6,190'. Circulate clean. Released plug. Rig down drilling head. Pull out of hole with 194 jts tubing. Laid down bridge plug. Run in hole with 2 3/8" mule shoe collar, 1 jt tubing, seating nipple and 195 jts. Pick up 12 jts tubing checking for plug back TD. Tagged sand at 6,615'. Bottom perforation at 6,625'. Pull out of hole with 10 jts tubing. Control well with 150 bbls 2% KCL water. Run in hole with 10 jts. Broke circulation. Clean sand from 6,615' to 6,681'. Circulate hole clean. Pull out of hole. Lay down 14 jts 2 3/8" tubing. Land tubing with 2 3/8" tubing hanger. Set tubing with seating nipple at 6,201' and end of tubing at 6,234'. Nipple down BOP. Nipple up tree. Rig up swab equipment. Made 14 runs. Flow 1st run at 1,000'. Last run at 2,800'. Swab back estimated 70 bbls. Well started flowing. Flow for 1/2 hour 2" stream. Install 24/64 choke. Left tubing flowing to pit. Flowing tubing to pit on 24/64 choke with 775 PSI on tubing and 1075 PSI on casing returning gas at the rate of 2,853 MCF/D, will burn. Small mist of water. Flow well another day to unload. Control water. Flowing tubing to pit on 24/64 choke with 750 PSI on tubing and 1050 PSI on casing returning gas at the rate of 2,761 MCF/D, will burn dry.

14. I hereby certify that the forgoing is true and correct

Signed

Susan M. Hebert
Susan M. Hebert

Title

Regulatory Reports Asst. II

Date

April 2, 1993

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
BUDGET BUREAU NO. 1004-0135

IRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32391
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Initial Production	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Well was placed on initial production on April 14, 1993 at 1:20 PM.

Note: Verbal notification of initial production telephoned into BLM by Sue Hebert, CNG. Information given to Sally Gardner, BLM on April 16, 1993, 11:18 AM.

RECEIVED

APR 20 1993

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the forgoing is true and correct

Signed Susan Hebert Title Regulatory Reports Asst. II Date April 15, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

**CNG Producing
Company**

A **CNG** COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

RECEIVED

APR 30 1993

April 27, 1993

DIVISION OF
OIL GAS & MINING

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: River Bend Unit
Well Recompletion Reports
RBU 3-3E NE NW of Sec. 3-T10S-R19E
RBU 7-10E SW NE of Sec. 10-T10S-R19E
RBU 11-14F NE SW of Sec. 14-T10S-R20E
RBU 2-23F NW NE of Sec. 23-T10S-R20E

Dear Ed:

Enclosed please find the original and two copies of the above referenced reports.

CNG Producing Company is requesting all information be held confidential.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Scot Childress at (504) 593-7574.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: Ms. Tammy Searing - Utah Department of Oil, Gas & Mining
Y. Abadie
S. Childress
B. Coffin
C. Collins
V. Corpening
D. Daly
D. Kulland
R. Mueller
J. Nicas
RBU Well Files
RBU Well Book
PG&E Resource Company

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ Other ☐

1b. TYPE OF COMPLETION: NEW WORK DEEP- PLUG DIFF. **RECEIVED**
WELL ☒ OVER ☐ EN ☐ BACK ☐ RESVR. ☐

2. NAME OF OPERATOR

CNG Producing Company

3. ADDRESS OF OPERATOR

CNG Tower - 1450 Poydras St., New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E

At top prod. interval reported below 808' 6680' Chg of Loc. 11-12-92

At total depth

5. LEASE DESIGNATION AND SERIAL NO.

U-01470-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

River Bend Unit

8. FARM OR LEASE NAME

RBU

9. WELL NO.

2-23F

10. FIELD AND POOL, OR WILDCAT Island

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

NW of NE of 23-T10S-R20E

14. PERMIT NO.

43-047-32391

DATE ISSUED

10/13/92

12. COUNTY OR PARISH

Uintah

13. STATE

Utah

15. DATE SPUNDED

12/11/92

16. DATE T.D. REACHED

12/25/93

17. DATE COMPL (Ready to prod.)

03/31/93

18. ELEVATION (OF RKB, RT, GR, ETC.)

5,101' GR

19. ELEV. CASING HEAD

20. TOTAL DEPTH MD & TVD

6,900'

21. PLUG, BACK T.D. MD & TVD

6,753'

22. IF MULTIPLE COMPL., HOW MANY*

3 Zones

23. INTERVALS DRILLED BY

----->

ROTARY TOOLS

Rotary

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)*

6,616-28', 6,262-70', 6,060-84', 5,970-82' & 5,626-54' - Wasatch

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

DLL, Den-Neu, GR, Cal MUD LOG 2-17-93

27. WAS WELL CORED

No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB/FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8 5/8"	24#	389'	12 1/4"	224 sks Class "G" Poz. Displace with 21 bbls water	
5 1/2"	17# N-80	6,876'		440 sks HiLift, 3% D-44, .8% D-20, 10#/sk D-42, .25#/sk D-2	
				1% D-79, .7% D-112 & .2% D-46 followed by 650 sks 10-0 F	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	5,551'	None

31. PERFORATION RECORD (Interval, size and number)

Zone #1 - 6,262-70' & 6,616-28'
Zone #2 - 5,970-80' & 6,076-84'
Zone #3 - 5,634-52'

CONFIDENTIAL

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
Zone #1	120,600 lbs of 20/40 Frac Sand
Zone #2	150,200 lbs of 20/40 Frac Sand
Zone #3	121,400 lbs of 20/40 Frac Sand

33. PRODUCTION

DATE FIRST PRODUCTION	PRODUCTION MET (Flowing, gas lift, pumping - size and type of pump)					WELL STATUS (Producing or shut-in)	
04/14/93	Flowing					Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL-BBL.	GAS-MCF.	WATER-BBL.	GAS-OIL RATIO
04/20/93	24	10/64	----->	-	710	-	-
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24 HR RATE	OIL-BBL.	GAS-MCF.	WATER-BBL.	OIL GRAVITY-APT (CORR.)	
1650	1650	----->	-	710	-	-	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold

TEST WITNESSED BY
Mitch Hall

35. LIST OF ATTACHMENTS

36. Thereby certify that the foregoing and attached information is complete and correct as determined from all available records.

SIGNED

W. Scot Childress
W. Scot Childress

TITLE Supervisor, Prod. Eng.

DATE April 23, 1993

*(See Instruction and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

GEOLOGICAL MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	TOP	
				MEAS. DEPTH	TRUE VERT. DEPTH
Wasatch	6,616'	6,628'	ss, wht-gy, vfn-fn gr, sub rd-sub ang., calcareous		
Wasatch	6,262'	6,270'	aa	3,969'	3,969'
Wasatch	6,198'	6,204'	aa	4,306'	4,306'
Wasatch	6,060'	6,084'	aa	4,454'	4,454'
Wasatch	5,970'	5,982'	aa	5,198'	5,198'
Wasatch	5,626'	5,654'	aa	6,280'	6,280'
Wasatch	5,370'	5,418'	aa		
Wasatch	5,106'	5,150'	aa		
Wasatch	5,040'	5,060'	aa		
Wasatch	4,925'	4,938'	aa		
Wasatch	4,884'	4,894'	aa		

**CNG Producing
Company**

A CNG COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

September 28, 1994

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: Well Completion or Recompletion Report
RBU 2-23F NW NE of Sec. 23-T10S-R20E
RBU 11-21F NW SW of Sec. 21-T10S-R20E
RBU 15-22E SW SE of Sec. 22-T10S-R19E
RBU 6-18F SE NW of Sec. 18-T10S-R20E
RBU 7-17F SW NE of Sec. 17-T10S-R20E
RBU 13-18F SW SW of Sec. 18-T10S-R20E

Dear Ed:

Enclosed please find the original and two copies of the above referenced reports.

CNG Producing Company is requesting all information be held confidential.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Scot Childress at (504) 593-7574.


Sincerely,

CNG PRODUCING COMPANY

Susan H. Sachitana
Susan H. Sachitana
Regulatory Specialist

Enclosure

cc: Utah Department of Oil, Gas & Mining
Y. Abadie
S. Childress
B. Coffin
C. Collins
V. Corpening
D. Daly
D. Davis
D. Kulland
RBU Well Files
RBU Well Book
PG&E Resource Company



UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE
(See other in-
structions on
reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ Other ☐

1b. TYPE OF COMPLETION: NEW WORK DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other ☐
WELL ☐ OVER ☒

2. NAME OF OPERATOR
CNG Producing Company

3. ADDRESS OF OPERATOR
CNG Tower - 1450 Poydras St., New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with BLM State Regulations)
At surface 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E

At top prod. interval reported below 208' 2286' 11-12-92 FT65Chg

At total depth

5. LEASE DESIGNATION AND SERIAL NO.
U-01470-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
River Bend Unit

8. FARM OR LEASE NAME
RBU

9. WELL NO.
2-23F

10. FIELD AND POOL, OR WILDCAT Island

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

NW of NE of 23-T10S-R20E

14. PERMIT NO.
43-047-32391

10/13/92

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

15. DATE SPUN
12/11/92

16. DATE T.D. REACHED
12/25/93

17. DATE COMF (Ready to prod.)
09/25/94

18. ELEVATION OF RKB, RT, GR, ETC.*
5,101' GR

19. ELEV. CASING HEAD

20. TOTAL DEPTH MD & TVD
6,900'

21. PLUG, BACK T.D. MD & TVD
6,650'

22. IF MULTIPLE COMPL., HOW MANY*
6 Zones

23. INTERVALS DRILLED BY
Rotary

ROTARY TOOLS

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)*
6,262-70', 6,616-26', 5,970-80', 6,076-84', 5,634-90' (old perfs)
5,376-90', 5,040-50', 5,112-22', 4,884-94' & 4,924-34' (new perfs) - Wasatch

25. WAS DIRECTIONAL SURVEY MADE
No

26. TYPE ELECTRIC AND OTHER LOGS RUN
DLL, Den/Neu, GR, Caliper

27. WAS WELL CORED
No

CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8 5/8"	24#	389'	12 1/4"	224 sks Class "G" Poz. Displace with 21 bbls water	"
5 1/2"	17# N-80	6,876'		440 sks HiLift, 3% D-44, .8% D-20, 10#/sk D-42, .25#/sk D-2	
				1% D-79, .7% D-112 & .2% D-46 followed by 650 sks 10-0 F	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	7,777'	5,290'

31. PERFORATION RECORD (Interval, size and number)

Zone #1 - 5,262-70' & 5,616-26'
Zone #2 - 5,970-80' & 6,076-84'
Zone #3 - 5,634-52'
Zone #4 - 5,376-90'
Zone #5 - 5,040-50' & 5,112-22'
Zone #6 - 4,884-94' & 4,924-34'

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
Zone #1	120,600 lbs of 20/40 Frac Sand
Zone #2	150,200 lbs of 20/40 Frac Sand
Zone #3	121,400 lbs of 20/40 Frac Sand
Zone #4	151,140 lbs of 20/40 Frac Sand
Zone #5	205,880 lbs of 20/40 Frac Sand
Zone #6	155,850 lbs of 20/40 Frac Sand

33. PRODUCTION

04/14/93		Flowing				Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL-BBL.	GAS-MCF.	WATER-BBL.	GAS-OIL RATIO
09/25/94	24	12/64	----->	-	1,559	-	-
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24 HR RATE	OIL-BBL.	GAS-MCF.	WATER-BBL.	OIL GRAVITY-API (CORR.)	
1600	0	----->	-	1,559	-	-	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)
Sold

TEST WITNESSED BY
Mitch Hall

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

SIGNED
W. Scott Childress

TITLE Supervisor, Prod. Eng.

DATE 09/23/94

*(See Instruction and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries)

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	GEOLOGICAL MARKERS		
				NAME	MEAS. DEPTH	TRUE VERT. DEPTH
Wasatch	6,616'	6,628'	ss, wht-gy, vfn-fn gr, sub rd-sub ang., calcareous	Wasatch Tongue	3,969'	3,969'
Wasatch	6,262'	6,270'	aa	Green River Tongue	4,306'	4,306'
Wasatch	6,198'	6,204'	aa	Wasatch	4,454'	4,454'
Wasatch	6,060'	6,084'	aa	Chapita Wells	5,198'	5,198'
Wasatch	5,970'	5,982'	aa	Uteland Buttes	6,280'	6,280'
Wasatch	5,626'	5,654'	aa			
Wasatch	5,370'	5,418'	aa			
Wasatch	5,106'	5,150'	aa			
Wasatch	5,040'	5,060'	aa			
Wasatch	4,925'	4,938'	aa			
Wasatch	4,884'	4,894'	aa			

WELL: 2-23F
FIELD: RBU
SECTION: 23, T10S, R20E
COUNTY: UINTAH
STATE: UTAH
ELEVATION: 5087'
KB TO FLANGE:
INPUT DATE: 4/18/94
ENGINEER: SCOT CHILDRESS
COMPLETION DATE: 9/25/94

**CNG PRODUCING
NEW ORLEANS**

CURRENT

TUBING: 2 3/8"

= ZONE VI
4884-94 and 4924-34
156M #'S 20/40
50 MCFPD
= ZONE V
5040-50 and 5112-22
206M #'S 20/40
1/4" STREAM OF WATER
= ZONE IV
5376-90
151M #'S 20/40
TESTED @ 1600 MCFPD

= ZONE III
5634-52
FRAC'D W/ 122M#'S 20/40
918 BF BORATE
TESTED @ 2.2 MMCFPD
EOT: 6214' OTIS PKR @ 5228'

= ZONE II
5970-5980
6076-6084
FRAC'D W/ 150M#'S 20/40
1296 BF BORATE
TESTED 900 MCFPD

= ZONE I
6262-70
6616-26
FRAC'D W/ 122M#'S 20/40
742 BF BORATE
TESTED @ 680 MCFPD

PBTD:

CASING/DEPTH: 5 1/2" 17# @ 6864'

**CNG Producing
Company**

A CNG COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

October 17, 1994

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: Well Completion or Recompletion Report
RBU 13-10F SW SW of Sec. 10-T10S-R20E
RBU 9-14EO NE SE of Sec. 14-T10S-R19E
RBU 5-24EO SW NW of Sec. 24-T10S-R19E
Subsequent Report Sundries
RBU 13-10F SW SW of Sec. 10-T10S-R20E
RBU 7-17F SW NE of Sec. 17-T10S-R20E
RBU 6-18F SE NW of Sec. 18-T10S-R20E
RBU 13-18F SW SW of Sec. 18-T10S-R20E
RBU 11-21F NW SW of Sec. 21-T10S-R20E
RBU 15-22E SW SE of Sec. 22-T10S-R19E
RBU 2-23F NW NE of Sec. 23-T10S-R20E

Dear Ed:

Enclosed please find the original and two copies of the above referenced reports.

CNG Producing Company is requesting all information be held confidential.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Scot Childress at (504) 593-7574.

Sincerely,

CNG PRODUCING COMPANY

Susan H. Sachitana
Susan H. Sachitana
Regulatory Specialist

OCT 18

Enclosure

cc: Utah Department of Oil, Gas & Mining
Y. Abadie
S. Childress
B. Coffin
C. Collins
D. Daly
D. Davis
D. Kulland
RBU Well Files
RBU Well Book
PG&E Resource Company

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation RBU
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 2-23F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32391
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E 858' 2286'	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CONFIDENTIAL

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Workover Report	<input type="checkbox"/> Dispose Water
		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Work started 6/28/94 and was completed 9/24/94.

1. Perforated Zone 4, 5,376-90' at 2 SPF.
2. Frac'd Zone 4 with 151,000 lbs of 20/40 frac sand.
3. Flowed and tested well at 1.6 MCF/D.
4. Set plug and perforated Zone 5, 5,040-50' & 5,112-22' (20 holes).
5. Frac'd with 206,000 lbs of 20/40 frac sand.
6. Flowed back 1/4" stream of water.
7. Set plug and perforated Zone 6, 4,884-94' & 4,824-34' (20 holes).
8. Frac'd with 156,000 lbs of 20/40 frac sand.
9. Flowed and tested at 50 ft3/d.
10. Pulled all plugs and completed as per schematic.

OCT 13

14. I hereby certify that the foregoing is true and correct

Signed Scot Childress Title Supervisor, Prod. Eng. Date October 11, 1994

Scot Childress

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

WELL: 2-23F

FIELD: RBU

SECTION: 23, T10S, R20E

COUNTY: UINTAH

STATE: UTAH

ELEVATION: 5087'

KB TO FLANGE:

INPUT DATE: 4/18/94

ENGINEER: SCOT CHILDRESS

COMPLETION DATE: 9/25/94

CNG PRODUCING
NEW ORLEANS

CONFIDENTIAL

CURRENT

TUBING: 2 3/8"

ZONE VI

= 4884-94 and 4924-34
156M #'S 20/40
50 MCFPD

ZONE V

= 5040-50 and 5112-22
206M #'S 20/40
1/4" STREAM OF WATER

ZONE IV

= 5376-90
151M #'S 20/40
TESTED @ 1600 MCFPD

ZONE III

= 5634-52
FRAC'D W/ 122M#'S 20/40
918 BF BORATE
TESTED @ 2.2 MMCFPD
EOT: 6214' OTIS PKR @ 5228'

ZONE II

= 5970-5980
6076-6084
FRAC'D W/ 150M#'S 20/40
1296 BF BORATE
TESTED 900 MCFPD

ZONE I

= 6262-70
6616-26
FRAC'D W/ 122M#'S 20/40
742 BF BORATE
TESTED @ 680 MCFPD

PBTD:

CASING/DEPTH: 5 1/2" 17# @ 6864'

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVERBEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 982' FNL & 1,438' FEL of Sec. 23-T10S-R20E		8. Well Name and No. 2-23F
		9. API Well No. 43-047-32391
		10. Field and Pool, or Exploratory Area ISLAND
		11. County or Parish, State UINTAH, UTAH


12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon _____
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input checked="" type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

CNG Producing Company proposes to store brine water from the above referenced well in a 100 bbl tank on the well site. As the tank fills, water will be hauled and disposed of into the RBU 16-19F injection well in Sec. 19-T10S-R20E.

Attached is a revised site diagram for this well site.




14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title COORDINATOR, REGULATORY REPORTS
Signature <i>Susan H. Sachitana</i>	Date 970716

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



WELLHEAD (typ)




RBH 2-20F
RBH WS MU AB
4304732391005/
47401470A
NW NE Q3 10S 20E

7-21-97

BL, G, C, W
 (± 100')

LEGEND

- D = Oil Line
- G = Gas Line
- W = Water Line
- R = Relief Line (Pressure)
- C = Condensate Line
- V = Vent Line
- D = Drain Line
- M = Gas Meter
- P = Pump
- BP = Back Pressure Valve
- SWS = Sealed When Shipping
- SUS = Sealed Unless Shipping
- T = Heat Traced Line
- H = Heater
- BL = Buried Line
- ⋈ = Valve
- ⋈ = Check Valve
- SC = Sealed Closed Valve
- NC = Normally Closed
- BD = Blowdown Line



The site security plan is on file in CNGP's district office located at 1400 N. State St., Roosevelt, Utah. It can be inspected during office hours, from 8:30am thru 5:30pm, Monday thru Friday.

CNG PRODUCING COMPANY

RIVER BEND FIELD, Uintah County, Utah

not to scale
 date:

TYPICAL FLOW DIAGRAM

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.
SUBMIT IN TRIPLICATE - Other instruction on reverse side


1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVERBEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 808 2286 Surface 388 FNL & 1486 FEL of Sec. 23-T10S-R20E		8. Well Name and No. 2-23F
		9. API Well No. 43-047-32391
		10. Field and Pool, or Exploratory Area ISLAND
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>PLUNGER LIFT</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

Installed plunger lift equipment on above well. Well on plunger as of 11/25/97.



14. I hereby certify that the forgoing is true and correct	
Name (Printed/Typed) SUSAN H. SACHITANA	Title COORDINATOR, REGULATORY REPORTS
Signature <i>Susan H. Sachitana</i>	Date 980120
THIS SPACE FOR FEDERAL OR STATE OFFICE USE	
Approved by	Title Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.	



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

DIVISION OF
OIL, GAS AND MINERAL

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS-Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL ☐ GAS ☐ OTHER:

2. Name of Operator:
DOMINION EXPLORATION & PRODUCTION, INC.

3. Address and Telephone Number:
1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260

4. Location of Well
Footages:
QQ, Sec, T., R., M.:

5. Lease Designation and Serial Number:
VARIOUS

6. If Indian, Allottee or Tribe Name:

7. Unit Agreement Name:

8. Well Name and Number:
VARIOUS

9. API Well Number

10. Field and Pool, or Wildcat:
Natural Buttes 630

County: UINTAH
State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(SUBMIT IN DUPLICATE)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |

Approximate date work will start

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other | OPERATOR NAME CHANGE FOR WELLS |

Date of work completion

Report results of Multiple Completion and Recompletion to different reservoirs on WELL
COMPLETION OR RECOMPLETION REPORT AND LOG form.

*Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.

John R. Lewis

Sr. Vice-President - CNG Producing Company


RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**

13.

Name & Signature:


John R. Lewis

Title: Sr. Vice-President - Dominion Expl. & Prod., Inc.

Date: June 26, 2000

(This space for State use only)

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**



State of Utah
DEPARTMENT OF COMMERCE
Division of Corporations & Commercial Code

File Number

Check Appropriate Box	
<input checked="" type="checkbox"/> Foreign Profit Corporation	\$35.00
<input type="checkbox"/> Foreign Non-Profit Corporation	\$35.00
<input type="checkbox"/> Foreign Limited Partnership	\$25.00
<input type="checkbox"/> Foreign Limited Liability Company	\$35.00

**Application To Amend The
CERTIFICATE OF AUTHORITY OR
REGISTRATION of**

CNG Producing Company
Business Entity Name

Delaware
Name of Home State

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.

The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- ☒ The name of the corporation is changing its name in Utah to the new name of the corporation in the home state.
☐ The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to: _____

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to: _____

IV. Other: _____

(Limited Partnership changing General Partners, Limited Companies changing Members or Managers. Change of statement who is managing, etc.)
Use an attached sheet if needed.

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

Signature

Vice President & Corporate Secretary
Title

April 20 2000
Date

State of Utah
Department of Commerce
Division of Corporations and Commercial Code

I hereby certify that the foregoing has been filed and approved on this 15 day of April 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner

Date



LEON JENSON
Division Director

Date: 04/25/2000

Receipt Number: 22156

Amount Paid: \$60.00

STATE OF UTAH
DIVISION OF CORPORATIONS
AND COMMERCIAL CODE
160 East 300 South / Box 146705
Salt Lake City, UT 84114-6705
Service Center: (801) 530-4849
Web Site: <http://www.commerce.state.ut.us>


FILED

APR 25 2000

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
RBU #11-21F	430473231500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-22E	430473231700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-19FX	430473232800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #2-11F	430473233100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-11F	430473234700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-16F	430473235200S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #2-23F	430473239100S1	DOMINION EXPLORATION & PR	PR	BLM

OPERATOR CHANGE WORKSHEET

Check each listed item when completed. Write N/A if item is not applicable.

	4-KAS ✓
2-CDW ✓	5- SP ✓
3-JLT	6-FILE

Change of Operator (Well Sold)

Designation of Agent

X Operator Name Change Only

Merger

The operator of the well(s) listed below has changed, effective: 4-12-00TO:(New Operator) DOMINION EXPL & PROD INC.FROM:(Old Operator) CNG PRODUCING COMPANYAddress: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Phone: 1-(504)-593-7000Phone: 1-(504)-593-7000Account No. N1095Account No. N0605

WELL(S):	CA Nos.	or	RIVER BEND	Unit
Name: <u>RBU 11-21F</u>	API: <u>43-047-32315</u>	Entity: <u>7050</u>	S <u>21</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-014352OA</u>
Name: <u>RBU 15-22E</u>	API: <u>43-047-32317</u>	Entity: <u>7050</u>	S <u>22</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013792</u>
Name: <u>RBU 3-19FX</u>	API: <u>43-047-32328</u>	Entity: <u>7050</u>	S <u>19</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013769-A</u>
Name: <u>RBU 2-11F</u>	API: <u>43-047-32331</u>	Entity: <u>7050</u>	S <u>11</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-01790</u>
Name: <u>RBU 3-11F</u>	API: <u>43-047-32347</u>	Entity: <u>7050</u>	S <u>11</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>
Name: <u>RBU 2-23F</u>	API: <u>43-047-32391</u>	Entity: <u>7050</u>	S <u>23</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793A</u>

OPERATOR CHANGE DOCUMENTATION

- YES 1. A pending operator change file has been set up.
- YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.
- YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.
- YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.
- YES 5. **Federal and Indian Lease Wells.** The BLM or the BIA has approved the merger, **name change** or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.

- N/A 8. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above.
- YES 9. Changes have been entered in the **Oil and Gas Information System** for each well listed on 7-31-00.
- YES 10. Changes have been included on the **Monthly Operator Change letter** on 7-31-00.

STATE BOND VERIFICATION

- N/A 1. State Well(s) covered by Bond No. _____.

FEE WELLS - BOND VERIFICATION / LEASE INTEREST OWNER NOTIFICATION

- N/A 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond.
- N/A 2. A **copy of this form** has been placed in the **new and former operator's bond files** on _____.
- N/A 3. The **FORMER** operator has requested a release of liability from their bond as of today's date _____? If yes, Division response was made to this request by letter dated _____. (see bond file).
- N/A 4. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated _____, of their responsibility to notify all interest owners of this change.
- N/A 5. Bond information added to **RBDMS** on _____.
- N/A 6. Fee wells attached to bond in **RBDMS** on _____.

FILMING

- _____ 1. All attachments to this form have been **microfilmed** on 2-23-01.

FILING

- _____ 1. **Originals/Copies** of all attachments pertaining to each individual well have been filed in each **well file**.
- _____ 2. The **original of this form** has been filed in the operator file and a copy in the old operator file.

COMMENTS

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ

2. CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2007

FROM: (Old Operator): N1095-Dominion Exploration & Production, Inc 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134 Phone: 1 (405) 749-1300	TO: (New Operator): N2615-XTO Energy Inc 810 Houston St Fort Worth, TX 76102 Phone: 1 (817) 870-2800
--	--

CA No.				Unit:		RIVER BEND		
WELL NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LIST								

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/6/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/6/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/6/2007
- a. Is the new operator registered in the State of Utah: Business Number: 5655506-0143
- b. If **NO**, the operator was contacted on: _____
- a. (R649-9-2) Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: _____
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: _____
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/27/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/27/2007
- Bond information entered in RBDMS on: 9/27/2007
- Fee/State wells attached to bond in RBDMS on: 9/27/2007
- Injection Projects to new operator in RBDMS on: 9/27/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/27/2007

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000138
- Indian well(s) covered by Bond Number: n/a
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 104312762
- b. The **FORMER** operator has requested a release of liability from their bond on: 1/23/2008

The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: XTO Energy Inc. <i>N2615</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 810 Houston Street CITY Fort Worth STATE TX ZIP 76102		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED		8. WELL NAME and NUMBER: SEE ATTACHED
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		9. API NUMBER: SEE ATTACHED
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input checked="" type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment from:

Dominion Exploration & Production, Inc.
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

N1095

James D. Abercrombie
James D. Abercrombie
Sr. Vice President, General Manager - Western Business Unit
(405) 749-1300

Please be advised that XTO Energy Inc. is considered to be the operator on the attached list and is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands. Bond coverage is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources Bond #104312762.

NAME (PLEASE PRINT) <u>Edwin S. Ryan, Jr.</u>	TITLE <u>Sr. Vice President - Land Administration</u>
SIGNATURE <i>Edwin S. Ryan, Jr.</i>	DATE <u>7/31/2007</u>

(This space for State use only)

APPROVED 9127107
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED
AUG 06 2007

DIV. OF OIL, GAS & MINING

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304730087	OSCU 2	NWSE	03	100S	200E	U-037164	7050	Federal	GW	P
4304730266	RBU 11-18F	NESW	18	100S	200E	U-013793	7050	Federal	GW	P
4304730374	RBU 11-13E	NESW	13	100S	190E	U-013765	7050	Federal	GW	P
4304730375	RBU 11-15F	NESW	15	100S	200E	U-7206	7050	Federal	GW	P
4304730376	RBU 7-21F	SWNE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304730405	RBU 11-19F	NESW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304730408	RBU 11-10E	NESW	10	100S	190E	U-013792	7050	Federal	GW	P
4304730410	RBU 11-14E	NESW	14	100S	190E	U-013792	7050	Federal	GW	P
4304730411	RBU 11-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304730412	RBU 11-16F	NESW	16	100S	200E	U-7206	7050	Federal	GW	P
4304730585	RBU 7-11F	SWNE	11	100S	200E	U-01790	7050	Federal	GW	P
4304730689	RBU 11-3F	NESW	03	100S	200E	U-013767	7050	Federal	GW	P
4304730720	RBU 7-3E	SWNE	03	100S	190E	U-013765	7050	Federal	GW	P
4304730759	RBU 11-24E	NESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304730761	RBU 7-10F	SWNE	10	100S	200E	U-7206	7050	Federal	GW	P
4304730762	RBU 6-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304730768	RBU 7-22F	SWNE	22	100S	200E	14-20-H62-2646	7050	Indian	GW	P
4304730887	RBU 16-3F	SESE	03	100S	200E	U-037164	7050	Federal	GW	P
4304730915	RBU 1-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304730926	RBU 1-14E	NENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304730927	RBU 1-22E	NENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304730970	RBU 1-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304730971	RBU 4-19F	NWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304730973	RBU 13-11F	SWSW	11	100S	200E	U-7206	7050	Federal	WD	A
4304731046	RBU 1-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	S
4304731115	RBU 16-16F	SESE	16	100S	200E	U-7206	7050	Federal	GW	P
4304731140	RBU 12-18F	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304731141	RBU 3-24E	NENW	24	100S	190E	U-013794	7050	Federal	GW	P
4304731143	RBU 3-23E	NENW	23	100S	190E	U-013766	7050	Federal	GW	P
4304731144	RBU 9-23E	NESE	23	100S	190E	U-013766	7050	Federal	GW	P
4304731145	RBU 9-14E	NESE	14	100S	190E	U-013792	7050	Federal	GW	P
4304731160	RBU 3-15E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304731161	RBU 10-15E	NWSE	15	100S	190E	U-013766	7050	Federal	GW	P
4304731176	RBU 9-10E	NESE	10	100S	190E	U-013792	7050	Federal	GW	P
4304731196	RBU 3-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304731252	RBU 8-4E	SENE	04	100S	190E	U-013792	7050	Federal	GW	P
4304731322	RBU 1-19F	NENE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304731323	RBU 5-10E	SWNW	10	100S	190E	U-013792	7050	Federal	GW	P
4304731369	RBU 3-13E	NENW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731518	RBU 16-3E	SESE	03	100S	190E	U-035316	7050	Federal	GW	P
4304731519	RBU 11-11F	NESW	11	100S	200E	U-7206	7050	Federal	GW	P
4304731520	RBU 1-17F	NENE	17	100S	200E	U-013769-B	7050	Federal	GW	P
4304731605	RBU 9-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	P
4304731606	RBU 3-22E	NENW	22	100S	190E	U-013792	7050	Federal	GW	P
4304731607	RBU 8-24E	SENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304731608	RBU 15-18F	SWSE	18	100S	200E	U-013794	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304731613	RBU 5-11F	SWNW	11	100S	200E	U-7206	7050	Federal	GW	P
4304731615	RBU 4-22F	NWNW	22	100S	200E	U-0143521-A	7050	Federal	GW	S
4304731652	RBU 6-17E	SWNW	17	100S	190E	U-03535	7050	Federal	GW	P
4304731715	RBU 5-13E	SWNW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731717	RBU 13-13E	SWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731739	RBU 9-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304732033	RBU 13-14E	SWSW	14	100S	190E	U-013792	7050	Federal	GW	P
4304732037	RBU 11-3E	NESW	03	100S	190E	U-013765	7050	Federal	GW	P
4304732038	RBU 6-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P
4304732040	RBU 15-24E	SWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304732041	RBU 5-14E	SWNW	14	100S	190E	U-013792	7050	Federal	GW	P
4304732050	RBU 12-20F	NWSW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732051	RBU 7-13E	SWNE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732070	RBU 16-19F	SESE	19	100S	200E	U-013769-A	7050	Federal	WD	A
4304732071	RBU 9-22E	NESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732072	RBU 15-34B	SWSE	34	090S	190E	U-01773	7050	Federal	GW	P
4304732073	RBU 11-15E	NESW	15	100S	190E	U-013766	7050	Federal	GW	P
4304732074	RBU 13-21F	SWSW	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732075	RBU 10-22F	NWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304732081	RBU 9-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732082	RBU 15-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P
4304732083	RBU 13-24E	SWSW	24	100S	190E	U-013794	7050	Federal	GW	P
4304732095	RBU 3-21E	NENW	21	100S	190E	U-013766	7050	Federal	GW	P
4304732103	RBU 15-17F	SWSE	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732105	RBU 13-19F	SWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732107	RBU 1-21E	NENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732128	RBU 9-21E	NESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732129	RBU 9-17E	NESE	17	100S	190E	U-03505	7050	Federal	GW	P
4304732133	RBU 13-14F	SWSW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732134	RBU 9-11F	NESE	11	100S	200E	U-7206	7050	Federal	GW	P
4304732138	RBU 5-21F	SWNW	21	100S	200E	U-013793	7050	Federal	GW	P
4304732146	RBU 1-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304732149	RBU 8-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P
4304732153	RBU 13-23E	SWSW	23	100S	190E	U-13766	7050	Federal	GW	P
4304732154	RBU 5-24E	SWNW	24	100S	190E	U-013794	7050	Federal	GW	P
4304732156	RBU 5-14F	SWNW	14	100S	200E	U-013793A	7050	Federal	GW	P
4304732166	RBU 7-15E	SWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304732167	RBU 15-13E	SWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732189	RBU 13-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304732190	RBU 15-10E	SWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304732191	RBU 3-17FX	NENW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732197	RBU 13-15E	SWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304732198	RBU 7-22E	SWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732199	RBU 5-23E	SWNW	23	100S	190E	U-013766	7050	Federal	GW	P
4304732201	RBU 13-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	S
4304732211	RBU 15-15E	SWSE	15	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304732213	RBU 5-19F	SWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732217	RBU 9-17F	NESE	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732219	RBU 15-14E	SWSE	14	100S	190E	U-013792	7050	Federal	GW	P
4304732220	RBU 5-3E	SWNW	03	100S	190E	U-03505	7050	Federal	GW	P
4304732228	RBU 9-3E	NESE	03	100S	190E	U-035316	7050	Federal	GW	P
4304732239	RBU 7-14E	SWNE	14	100S	190E	U-103792	7050	Federal	GW	P
4304732240	RBU 9-14F	NESE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732242	RBU 5-22E	SWNW	22	100S	190E	U-013792	7050	Federal	GW	P
4304732263	RBU 8-13E	SENE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732266	RBU 9-21F	NESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732267	RBU 5-10F	SWNW	10	100S	200E	U-7206	7050	Federal	GW	P
4304732268	RBU 9-10F	NESE	10	100S	200E	U-7206	7050	Federal	GW	P
4304732269	RBU 4-15F	NWNW	15	100S	200E	INDIAN	7050	Indian	GW	PA
4304732270	RBU 14-22F	SESW	22	100S	200E	U-0143519	7050	Federal	GW	P
4304732276	RBU 5-21E	SWNW	21	100S	190E	U-013766	7050	Federal	GW	P
4304732289	RBU 7-10E	SWNE	10	100S	190E	U-013792	7050	Federal	GW	P
4304732290	RBU 5-17F	SWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732293	RBU 3-3E	NENW	03	100S	190E	U-013765	7050	Federal	GW	P
4304732295	RBU 13-22E	SWSW	22	100S	190E	U-013792	7050	Federal	GW	P
4304732301	RBU 7-21E	SWNE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732309	RBU 15-21F	SWSE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732310	RBU 15-20F	SWSE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732312	RBU 9-24E	NESE	24	100S	190E	U-013794	7050	Federal	GW	P
4304732313	RBU 3-20F	NENW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304732315	RBU 11-21F	NESW	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732317	RBU 15-22E	SWSE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732328	RBU 3-19FX	NENW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732331	RBU 2-11F	NWNE	11	100S	200E	U-01790	7050	Federal	GW	P
4304732347	RBU 3-11F	NENW	11	100S	200E	U-7206	7050	Federal	GW	P
4304732391	RBU 2-23F	NWNE	23	100S	200E	U-013793-A	7050	Federal	GW	S
4304732392	RBU 11-14F	NESW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732396	RBU 3-21F	NENW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304732407	RBU 15-14F	SWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732408	RBU 4-23F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304732415	RBU 3-10EX (RIG SKID)	NENW	10	100S	190E	UTU-035316	7050	Federal	GW	P
4304732483	RBU 5-24EO	SWNW	24	100S	190E	U-013794	11719	Federal	OW	S
4304732512	RBU 8-11F	SENE	11	100S	200E	U-01790	7050	Federal	GW	P
4304732844	RBU 15-15F	SWSE	15	100S	200E	14-20-H62-2646	7050	Indian	GW	P
4304732899	RBU 3-14F	NENW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732900	RBU 8-23F	SENE	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304732901	RBU 12-23F	NWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304732902	RBU 1-15F	NENE	15	100S	200E	U-7260	7050	Federal	GW	S
4304732903	RBU 3-15F	NENW	15	100S	200E	U-7260	7050	Federal	GW	P
4304732904	RBU 9-15F	NESE	15	100S	200E	U-7260	7050	Federal	GW	P
4304732934	RBU 3-10F	NENW	10	100S	200E	U-7206	7050	Federal	GW	P
4304732969	RBU 11-10F	NESW	10	100S	200E	U-7206	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304732970	RBU 12-15F	NWSW	15	100S	200E	U-7206	7050	Federal	GW	P
4304732971	RBU 15-16F	SWSE	16	100S	200E	U-7206	7050	Federal	GW	S
4304732972	RBU 1-21F	NENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304732989	RBU 13-10E	SWSW	10	100S	190E	U-013792	7050	Federal	GW	P
4304732990	RBU 13-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304732991	RBU 6-19F	SENW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733033	RBU 7-23E	NWNE	23	100S	190E	U-013766	7050	Federal	GW	P
4304733034	RBU 9-18F	NESE	18	100S	200E	U-013794	7050	Federal	GW	P
4304733035	RBU 14-19F	SESW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733087	RBU 6-23F	SENW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304733088	RBU 1-10F	NENE	10	100S	200E	U-7206	7050	Federal	GW	P
4304733089	RBU 8-22F	SENE	22	100S	200E	U-0143521	7050	Federal	GW	P
4304733090	RBU 11-22F	NESW	22	100S	200E	U-0143519	7050	Federal	GW	P
4304733091	RBU 16-22F	SESE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304733156	RBU 4-14E	NWNW	14	100S	190E	U-013792	7050	Federal	GW	P
4304733157	RBU 7-19F	SWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733158	RBU 7-20F	SWNE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304733159	RBU 7-24E	SWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304733160	RBU 8-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304733161	RBU 16-10E	SESE	10	100S	190E	U-013792	7050	Federal	GW	P
4304733194	RBU 2-14E	NWNE	14	100S	190E	U-013792	7050	Federal	GW	P
4304733272	RBU 13-3F	SWSW	03	100S	200E	U-013767	7050	Federal	GW	P
4304733361	RBU 5-3F	SWNW	03	100S	200E	U-013767	7050	Federal	GW	P
4304733362	RBU 15-10F	SWSE	10	100S	200E	U-7206	7050	Federal	GW	P
4304733363	RBU 5-16F	SWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304733365	RBU 12-14E	NWSW	14	100S	190E	U-013792	7050	Federal	GW	P
4304733366	RBU 5-18F	SWNW	18	100S	200E	U-013769	7050	Federal	GW	P
4304733367	RBU 10-23F	NWSE	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304733368	RBU 14-23F	SESW	23	100S	200E	U-01470-A	7050	Federal	GW	S
4304733424	RBU 5-20F	SWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304733643	RBU 2-13E	NWNE	13	100S	190E	U-013765	7050	Federal	GW	P
4304733644	RBU 4-13E	NWNW	13	100S	190E	U-013765	7050	Federal	GW	P
4304733714	RBU 4-23E	NWNW	23	100S	190E	U-013766	7050	Federal	GW	P
4304733715	RBU 6-13E	SENW	13	100S	190E	U-013765	7050	Federal	GW	P
4304733716	RBU 10-14E	NWSE	14	100S	190E	U-013792	7050	Federal	GW	P
4304733838	RBU 8-10E	SENE	10	100S	190E	U-013792	7050	Federal	GW	P
4304733839	RBU 12-23E	NWSW	23	100S	190E	U-013766	7050	Federal	GW	P
4304733840	RBU 12-24E	NWSW	24	100S	190E	U-013794	7050	Federal	GW	P
4304733841	RBU 14-23E	SESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734302	RBU 1-23F	NENE	23	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304734661	RBU 16-15E	SESE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734662	RBU 10-14F	NWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304734663	RBU 6-14E	SENW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734670	RBU 8-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304734671	RBU 4-24E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304734701	RBU 12-11F	SENW	11	100S	200E	U-7206	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304734702	RBU 2-15E	NWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734703	RBU 4-17F	NWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734745	RBU 10-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734749	RBU 7-18F	SWNE	18	100S	200E	U-013769	7050	Federal	GW	P
4304734750	RBU 12-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304734810	RBU 10-13E	NWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734812	RBU 1-24E	NENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734826	RBU 12-21F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734828	RBU 4-15E	NWNW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734844	RBU 14-14E	SESW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734845	RBU 10-24E	NWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734888	RBU 4-21E	NWNW	21	100S	190E	U-013766	7050	Federal	GW	P
4304734889	RBU 16-24E	SESE	24	100S	190E	U-13794	7050	Federal	GW	P
4304734890	RBU 12-18F2	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734891	RBU 10-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734892	RBU 8-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734906	RBU 6-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734907	RBU 2-24E	NWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734910	RBU 4-16F	NWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304734911	RBU 12-19F	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734912	RBU 14-20F	SESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734942	RBU 1-22F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304734945	RBU 8-19F	SENE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734946	RBU 8-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304734962	RBU 12-17F	NWSW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734963	RBU 2-17F	NWNE	17	100S	200E	U-013769-C	14117	Federal	GW	P
4304734966	RBU 14-18F	SESW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734967	RBU 10-18F	NWSE	18	100S	200E	U-013794	7050	Federal	GW	P
4304734968	RBU 10-19F	NWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734969	RBU 10-3E	NWSE	03	100S	190E	U-035316	7050	Federal	GW	P
4304734970	RBU 12-3E	NWSW	03	100S	190E	U-013765	7050	Federal	GW	P
4304734971	RBU 15-3E	SWSE	03	100S	190E	U-35316	7050	Federal	GW	P
4304734974	RBU 12-10E	NWSW	10	100S	190E	U-013792	14025	Federal	GW	P
4304734975	RBU 14-10E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734976	RBU 16-13E	SESE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734977	RBU 8-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304734978	RBU 6-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734979	RBU 12-15E	NWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734981	RBU 16-17E	SESE	17	100S	190E	U-013766	7050	Federal	GW	P
4304734982	RBU 8-21E	SENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304734983	RBU 4-22E	NWNW	22	100S	190E	U-013792	7050	Federal	GW	P
4304734986	RBU 2-20F	NWNE	20	100S	200E	U-03505	7050	Federal	GW	P
4304734987	RBU 9-20E	SWNW	21	100S	190E	U-03505	7050	Federal	GW	P
4304734989	RBU 7-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304734990	RBU 8-20E	SWNW	21	100S	190E	U-03505	14164	Federal	GW	P
4304735041	RBU 16-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304735042	RBU 12-22E	NWSW	22	100S	190E	U-013792	14165	Federal	GW	P
4304735058	RBU 7-23F	SWNE	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304735059	RBU 12-13E	NWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735060	RBU 14-13E	SESW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735061	RBU 2-22E	NWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735062	RBU 6-24E	SENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304735082	RBU 4-17E	NWNW	17	100S	190E	U-03505	7050	Federal	GW	P
4304735086	RBU 16-14E	NENE	23	100S	190E	U-013792	7050	Federal	GW	P
4304735087	RBU 2-3E	NWNE	03	100S	190E	U-013765	7050	Federal	GW	P
4304735088	RBU 6-3E	SENE	03	100S	190E	U-03505	7050	Federal	GW	P
4304735100	RBU 10-10E	NWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304735101	RBU 16-22E	SESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735112	RBU 14-24E	SESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304735129	RBU 6-21F	SENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735170	RBU 1-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304735171	RBU 16-9E	NESE	09	100S	190E	U-013765	7050	Federal	GW	P
4304735232	RBU 14-21F	SESW	21	100S	200E	U-0143520	7050	Federal	GW	P
4304735250	RBU 13-19F2	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735251	RBU 15-19F	SWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735270	RBU 16-21E	SESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735304	RBU 13-20F	SWSW	20	100S	200E	U-013769	7050	Federal	GW	P
4304735305	RBU 4-21F	NWNW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735306	RBU 16-21F	SESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304735468	RBU 15-22F	SWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304735469	RBU 11-23F	SENE	23	100S	200E	U-01470A	7050	Federal	GW	P
4304735549	RBU 1-14F	NENE	14	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304735640	RBU 2-21E	NWNE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735644	RBU 10-17E	NWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304735645	RBU 12-21E	NWSW	21	100S	190E	U-013766	7050	Federal	GW	P
4304736200	RBU 8-17E	SWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736201	RBU 15-17EX	SWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736293	RBU 2-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	P
4304736294	RBU 6-10E	NENW	10	100S	190E	U-013792	7050	Federal	GW	P
4304736296	RBU 6-21E	SENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304736297	RBU 10-22E	NWSE	22	100S	190E	U-013792	7050	Federal	GW	P
4304736318	RBU 14-22E	SESW	22	100S	190E	U-013792	7050	Federal	GW	P
4304736427	RBU 9-15E	NESE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304736428	RBU 2-17E	NWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736429	RBU 1-17E	NENE	17	100S	190E	U-013766	7050	Federal	GW	DRL
4304736432	RBU 3-19F2	NWNW	19	100S	200E	U-013769-A	15234	Federal	GW	P
4304736433	RBU 14-17F	SESW	17	100S	200E	U-03505	7050	Federal	GW	P
4304736434	RBU 2-19F	NWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304736435	RBU 5-19FX	SWNW	19	100S	200E	U-013769-A	15855	Federal	GW	P
4304736436	RBU 4-20F	NWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304736605	RBU 16-14F	SESE	14	100S	200E	U-013793A	7050	Federal	GW	P
4304736608	RBU 4-3E	NWNW	03	100S	190E	U-035316	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304736609	RBU 8-3E	SENE	03	100S	190E	U-013765	7050	Federal	GW	P
4304736610	RBU 14-3E	SESW	03	100S	190E	U-013765	7050	Federal	GW	P
4304736686	RBU 13-3E	NWSW	03	100S	190E	U-013765	15235	Federal	GW	P
4304736810	RBU 1-3E	NENE	03	100S	190E	U-013765	7050	Federal	GW	DRL
4304736850	RBU 2-10F	NWNE	10	100S	200E	U-7206	7050	Federal	GW	P
4304736851	RBU 8-21F	SENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304737033	RBU 4-10E	SWNW	10	100S	190E	U-035316	7050	Federal	GW	P
4304737057	RBU 11-17E	NWSE	17	100S	190E	U-03505	7050	Federal	GW	DRL
4304737058	RBU 3-17E	NENW	17	100S	190E	U-03505	7050	Federal	GW	P
4304737201	RBU 3-23F	NENW	23	100S	200E	U-013793-A	7050	Federal	OW	P
4304737341	RBU 11-20F	NESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304737342	RBU 5-15F	SWNW	15	100S	200E	U-7206	7050	Federal	OW	P
4304737343	RBU 10-16F	NWSE	16	100S	200E	U-7206	7050	Federal	OW	P
4304737344	RBU 9-16F	NESE	16	100S	200E	U-7206	7050	Federal	OW	S
4304737450	RBU 14-17E	SESW	17	100S	190E	U-03505	7050	Federal	GW	P
4304737747	RBU 15-9E	NWNE	16	100S	190E	U-013765	7050	Federal	GW	DRL
4304737893	RBU 9-4EA	SENE	04	100S	190E	U-03505	7050	Federal	GW	P
4304737998	RBU 13-23F	SWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304738181	RBU 12-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL
4304738182	RBU 11-4E	SE/4	04	100S	190E	U-03505	99999	Federal	GW	DRL
4304738294	RBU 2-4E	NWNE	04	100S	190E	U-013792	7050	Federal	GW	DRL
4304738295	RBU 5-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL
4304738543	RBU 28-18F	NESE	13	100S	190E	U 013793-A	7050	Federal	GW	DRL
4304738548	RBU 32-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	DRL
4304738555	RBU 27-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738556	RBU 27-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738557	RBU 30-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304738558	RBU 29-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738595	RBU 31-10E	NENE	15	100S	190E	U-013792	7050	Federal	GW	DRL
4304738596	RBU 17-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304738780	RBU 8B-17E	SENE	17	100S	190E	U-013766	7050	Federal	GW	DRL

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304730153	NATURAL 1-2	SENW	02	100S	200E	ML-10716	11377	State	OW	PA
4304730260	RBU 11-16E	NESW	16	100S	190E	ML-13214	7050	State	GW	S
4304730583	RBU 11-36B	NESW	36	090S	190E	ML-22541	99998	State	NA	PA
4304730608	RBU 8-16D	SENE	16	100S	180E	ML-13216	99998	State	NA	PA
4304730760	RBU 11-2F	NESW	02	100S	200E	ML-10716	9966	State	OW	S
4304731740	RBU 1-16E	NENE	16	100S	190E	ML-13214	7050	State	GW	P
4304732026	RBU 16-2F	SESE	02	100S	200E	ML-10716	7050	State	GW	P
4304732042	RBU 9-16E	NESE	16	100S	190E	ML-13214	7050	State	GW	P
4304732108	RBU 14-2F	SESW	02	100S	200E	ML-10716	7050	State	GW	P
4304732136	RBU 8-2F	SENE	02	100S	200E	ML-10716	7050	State	GW	P
4304732137	RBU 5-16E	SWNW	16	100S	190E	ML-13214	7050	State	GW	P
4304732245	RBU 7-16E	SWNE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732250	RBU 13-16E	SWSW	16	100S	190E	ML-13214	7050	State	GW	S
4304732292	RBU 15-16E	SWSE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732314	RBU 10-2F	NWSE	02	100S	200E	ML-10716	7050	State	GW	P
4304732352	RBU 3-16F	NENW	16	100S	200E	ML-3393-A	7050	State	GW	P
4304733360	RBU 1-16F	NENE	16	100S	200E	ML-3393	7050	State	GW	P
4304734061	RBU 6-16E	SWNE	16	100S	190E	ML-13214	7050	State	GW	P
4304734167	RBU 1-2F	NENE	02	100S	200E	ML-10716		State	GW	LA
4304734315	STATE 11-2D	NESW	02	100S	180E	ML-26968		State	GW	LA
4304734903	RBU 14-16E	SWSW	16	100S	190E	ML-13214	7050	State	D	PA
4304735020	RBU 8-16E	SENE	16	100S	190E	ML-13214	7050	State	GW	P
4304735021	RBU 10-16E	SWSE	16	100S	190E	ML-13214	7050	State	GW	P
4304735022	RBU 12-16E	NESW	16	100S	190E	ML-13214	7050	State	GW	P
4304735023	RBU 16-16E	SWSW	15	100S	190E	ML-13214	7050	State	GW	P
4304735033	RBU 2-16E	NWNE	16	100S	190E	ML-13214	7050	State	GW	P
4304735081	RBU 15-2F	SWSE	02	100S	200E	ML-10716	7050	State	GW	P
4304735348	RBU 13-16F	NWNW	21	100S	200E	ML-3394	7050	State	GW	DRL
4304736169	RBU 4-16E	NENW	16	100S	190E	ML-13214	7050	State	GW	P
4304736170	RBU 3-16E	NENW	16	100S	190E	ML-13214	7050	State	GW	P



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

Dominion Exploration & Production, Inc.
Attn: James D. Abercrombie
14000 Quail Springs Parkway, #600
Oklahoma City, OK 73134-2600

August 10, 2007

Re: River Bend Unit
Uintah County, Utah

Gentlemen:

On August 8, 2007, we received an indenture dated June 30, 2007, whereby Dominion Exploration & Production, Inc. resigned as Unit Operator and XTO Energy Inc. was designated as Successor Unit Operator for the River Bend Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective August 15, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the River Bend Unit Agreement.

Your statewide oil and gas bond No. UTB000138 will be used to cover all operations within the River Bend Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble
Acting Chief, Branch of Fluid Minerals

Enclosure

RECEIVED
AUG 16 2007
DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-013793-A
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: RIVER BEND
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBV 2-23F
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047323910000
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155	PHONE NUMBER: 303 397-3727 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0808 FNL 2286 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 23 Township: 10.0S Range: 20.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/6/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. intends to plug & abandon this well per the attached procedure. Also attached, please see current & proposed wellbore diagrams.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: October 06, 2014

By: Derek Duff

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 303-397-3736	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 9/26/2014	

River Bend Unit 02-23F
Plug and Abandonment AFE# 1408471
Section 23; Township 10S; Range 20E
API: 43-047-32391
Uintah County, Utah

Elevation: 5101' GL; 5115' KB

Tubular Details:

Pipe String	Hole Size (in)	OD (in) / Grade	Weight (ppf)	Drift ID (in)	Cap. (cf/ ft)	Cap. (bbl/ ft)	Annular Cap. (bbl/ft)	Depth (ft)	Detail
Surf Csg	12-1/4	8-5/8 H-40	24	7.972	0.3575	0.0636	--	389	224 sks Class "G" cement
Prod Csg	7-7/8	5-1/2 N-80	17	4.767	0.1305	0.0232	0.0343	6897	1090 sks Hi-Lift cement
Prod Tbg	--	2-3/8 J-55	4.7	1.901	0.0217	0.00387	0.0178	6214	Otis compression packer @ 5290'

Perforation Detail:

Formation	Perf Interval, MD (ft)
Wasatch	4884-4894; 4924-4934; 5040-5050; 5112-5122; 5376-5390; 5634-5652; 5970-5980; 6076-6084; 6262-6270; 6616-6626

Well Status: Shut in

Plugging Procedure:

COMPLY WITH ALL STATE, BLM, AND XTO SAFETY REGULATIONS

P&A Operation Notes:

- All cement volumes use 100% excess outside pipe & 50' excess inside pipe.
- The wellbore fluid used for abandonment operations in the wellbore will be 9.0 ppg treated fluid (biocide & corrosion inhibited with 5 gal/100 bbl each) to balance exposed formations.
- Cement will be Class G or equivalent, as specified by regulations, mixed at 15.8 ppg and 1.18 cf/sk yield with 2% CaCl and 0.25 lb/sk celloflake additives.
- The wellbore 'surface' is referred to as 3' below ground level due to final csg removal depth requirements.

1. Remove any remaining surface equipment off wellsite.

2. Install and test location rig anchors.
3. MIRU P&A rig. Conduct safety meeting for all personnel on location. Record casing, tubing and bradenhead pressures.
4. NU relief line and BD well. RU pumping equipment to tbg and pressure test lines. Pump at least tubing volume of water to kill well.
5. ND WH and NU BOP. Function test BOP.
6. Pick up on tubing to release Otis M.H. compression packer and TOH tbg. If packer will not release:
 - a. Cut tubing with chemical cutter at ~5280'. TOH with chemical cutter and tbg.
 - b. PU basket grapple, overshot, jars, intensifiers, bumper sub, drill collars, and tbg. TIH and latch onto fish. Jar on fish until loose. If packer will not release, TOH tbg and BHA.
 - c. PU mill and washover shoe. TIH and mill on packer until free. TOH and LD mill. PU basket grapple, overshot, jars, intensifiers, bumper sub, drill collars, and tbg. Latch onto fish, TOH and LD packer.
7. Round trip bit & scraper. PT tbg during run to determine integrity.
8. PU and TIH CICR. Set @ 4400' (do not set in csg collar). Circulate WS with treated water above CICR and ensure csg is filled to surface. Pressure test csg to 500 psi to determine integrity.
9. **Plug #1, Isolate Wasatch Perforations and Top (Formation top @ 4449')**: Sting WS into CICR, mix 22 sack of Class G cement (4.6 bbls) and pump 14 sacks (2.9 bbls) below CR, sting out and spot the remaining 8 sacks (1.7 bbls) above CICR. *This leaves 100'+excess cement below CICR and 50'+excess above, TOC @ +/- 4350'.*
10. TOH with WS. While WOC of Plug #1, Run CBL from +/- 4300' to surface to confirm TOC of production csg.
11. TIH, Tag TOC.
12. **Plug #2, Isolate Parachute Creek Oil Shale (Base @ 2317')**: Pull WS up to 2417'. Mix 28 sks of Class G cement slurry (5.9 bbls) and set a 200'+excess balanced plug inside 5-1/2" production csg from 2417' to 2217'.
13. **Plug #3, Isolate Green River Top (Formation top @ 1078')**: Pull WS up to 1178'. Mix 28 sks of Class G cement slurry (5.9 bbls) and set a 200'+excess balanced plug inside 5-1/2" production csg from 1178' to 978'.

14. **Plug #4, Casing Shoe to Surface:** RU pumps to bradenhead casing (8-5/8" x 5-1/2" annulus) and pump to fill BH annulus volume and note any leak off. If no injection or leakoff is established, TIH with WS to 439'. Mix 54 sks of Class G cement slurry (11.3 bbls) and spot a balanced plug inside 5-1/2" production csg from 439' – surface.
 - a. If injection or leakoff of BH annulus , RU W/L and perf 3 HSC squeeze holes @ 439'. RD W/L. RU pumps to 5-1/2" csg, establish circulation down 5-1/2" casing and take returns at the bradenhead valve. Circulate the BH annulus clean. Mix 134 sks of Class G cement slurry (28.1 bbls) and pump down the 5.5" casing; circulate cement to surface on BH casing annulus and spot balanced plug in 5-1/2" to surface.
15. Remove WH and cut csg strings at 3' below surface. Top out as necessary. Install P&A marker to comply with regulations.
16. RMDO workover rig. Clean up location. Prepare for site reclamation within 6 months of final wellbore abandonment operations.

RBU 02-23F

Current Sketch


Natural Buttes Field
2,286' FEL, 808' FNL, Section 23, T10S, R20E
Uintah County, UT
API# 43-047-32391

Today's Date: 9/17/14

Spud: 12/11/92

Completed:

Elevation: 5101', 5115' KB



RBU 02-23F

Proposed P&A

Natural Buttes Field

2,286' FEL, 808' FNL, Section 23, T10S, R20E

Uintah County, UT


API# 43-047-32391

Today's Date: 9/17/14

Spud: 12/11/92

Completed:

Elevation: 5101', 5115' KB



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-013793-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		7. UNIT or CA AGREEMENT NAME: RIVER BEND
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155		8. WELL NAME and NUMBER: RBV 2-23F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0808 FNL 2286 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 23 Township: 10.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047323910000
PHONE NUMBER: 303 397-3727 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/29/2014			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. has plugged & abandoned this well per the attached summary report. Reclamation work will begin ASAP this fall according to the XTO Reclamation Plan on file at the Vernal BLM.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

November 12, 2014

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 303-397-3736	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 11/7/2014	

Riverbend Unit 02-23F

10/26/2014: MIRU. Ppd dwn csg w/50 bbls TFW, for well cont. ND WH. NU & FT BOP. Att to rels pkr w/no succ. SWI & SDFN

10/27/2014: Att to rls 5-1/2" pkr, free w/no succ. Make decision to cut tbg @ 4,700'. (10/27/14), Got verbal approval fr/BLM to leave fish in hole. MIRU EL. RU & RIH w/1.8" GR to 4,800'. POH w/GR. RU RIH w/1-11/16" jet cutter. Cut 2-3/8" tbg @ 4,700'. POH w/EL & jet cutter. RDMO EL. TOH strapping w/147 jt's 2-3/8" tbg & 2-3/8" x 16' cut off piece of 2-3/8" tbg. (tbg cut was belled out fr/jet cutter). PU & TIH w/4-3/4" bit, 5-1/2" csg scr, 2-3/8" SN & 140 jts 2-3/8" tbg. EOT @ 4,459'. TOH w/bit & scr. SWI & SDFN.

10/28/2014: PU & TIH w/5-1/2" CICR, 138 jts 2-3/8" tbg & 2-3/8" x 8' tbg sub. EOT @ 4,400'. Set CICR @ 4,400'. PT tbg to 1,000 psig. Estb EIR of 3.5 BPM @ 500 psig, through cicr @ 4,400'. Unsting fr/CICR & Circ 5-1/2" csg w/100 bbls TFW mixd w/biocide & corr inhib. PT 5-1/2" csg to 500 psig, 10" Tstd ok. Glade Rich w/BLM was a witness for PT. Plg #1. Mix & Ppd dwn tbg w/26 sks class b cmnt, 1.18 yld, spt 14 sks below CICR & 12 sks on top. (107' on top CICR & 126' below Est cmnt top @ 4,293'). TOH w/138 jts 2-3/8" tbg & stinger. MIRU A plus EL. RU & RIH w/CBL. Log well fr/4,200' - surf. Log showed 95% cmnt bond fr/4,200' - 1,370' & 80% cmnt bond to 978, all above free pipe. Est cmnt top @ 978'. RDMO A plus EL. TIH w/110 jts 2-3/8" tbg. EOT @ 3,500'. Plg #2. Mix & Ppd dwn tbg w/17 sks class b cmnt, 1.18 yld, spt balanced plg @ 3,500' - 3,348'. TOH w/35 jts 2-3/8" tbg. EOT @ 3,401'. SWI & SDFN.

10/29/2014: TIH w/35 jts 2-3/8" tbg, tg TOC fr/plg #2 @ 3,359'. TOH LD 31 jt's 2-3/8" tbg. EOT @ 2,417'. Plg #3. Mixd & pmp dwn tbg w/28 sks class b cmt, 1.18 yld. Spt balanced plg fr/2,417' - 2,164'. TOH LD 39 jts 2-3/8" tbg. EOT @ 1,178'. Plg #4. Mix & pmp dwn tbg w/28 sks class b cmt, 1.18 yld. Spt balanced fr/1,178' - 925'. TOH LD 40 jts 2-3/8" tbg. MIRU A Plus EL. RIH w/3-1/8" csg gun w/120 deg phasing. Perf 3 squeeze holes in fr/439' - 40'. POH w/csg gun. Pmp dwn 5-1/2" csg w/8 BFW & estb circ fr/8-5/8" csg @ 2 BPM & 700 psig. Circ cln w/28 BFW. Plg #5. Mix & pmp dwn 5-1/2" csg w/140 sks class b cmt, 1.18 yld. Lost circ after pmping 22 bbls cmt. Cont ppg w/5 bbls cmt & SD. ND BOP. Cut off 8-5/8" csg head. Found TOC in 5-1/2" csg @ 100' FS & 50' FS in 5-1/2" x 8-5/8" csg annl. RIH w/1-1/4" polly pipe & topped both csg strgs w/36 sx type b cmt. BLM was a witness. Will weld marker plate on later. RDMO.

=====Riverbend Unit 02-23F=====

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-013793-A			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: RIVER BEND			
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: RBW 2-23F			
3. ADDRESS OF OPERATOR: PO Box 6501, Englewood, CO, 80155		9. API NUMBER: 43047323910000			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0808 FNL 2286 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 23 Township: 10.0S Range: 20.0E Meridian: S		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		COUNTY: UINTAH STATE: UTAH			
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 11/25/2014 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has completed final reclamation of this well site per the attached summary report.					
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY January 08, 2015					
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 303-397-3736	TITLE Regulatory Analyst			
SIGNATURE N/A	DATE 12/12/2014				

Riverbend Unit 02-23F

11/18/2014: Started pulling up fill slopes to reclaim location

11/19/2014: Pulling up fill slopes and recontouring location

11/20/2014: Cont. pulling up fill slopes and recontouring location

11/21/2014: Met with MSO to replace road crossing on access road. Start reclaiming access road out to main road. Cut & rmvd 250' of 4" 188W bare steel pipe gas line for reclamation then reinstalled 250' of 4" 188W bare steel pipe on gathering line. Put all wells back on line at 4:00pm.

11/25/2014: Reseeded location and access road. Seed was broadcast. 16-16-08 Fertilizer was added at 30 lbs to the acre.

Seed mix as follows:

Shadscale saltbrush - at 1.5 lbs per acre

Winterfar - at 1.5 lbs per acre

Gardner Saltbrush - 1.5 lbs per acre

Fourwing saltbrush - 1.5 lbs per acre

Munroe Globemallow - 0.5 lbs per acre

Slender Wheatgrass - 2 lbs per acre

Forage Kochia - 1 lb per acre

Indian Ricegrass - 2 lbs per acre

Bluebunch Wheatgrass - 2 lbs per acre

Russian Wildrye - 2 lbs per acre

=====Riverbend Unit 02-23F=====

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-013793-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		7. UNIT or CA AGREEMENT NAME: RIVER BEND
3. ADDRESS OF OPERATOR: PO Box 6501, Englewood, CO, 80155		8. WELL NAME and NUMBER: RBW 2-23F
PHONE NUMBER: 303 397-3727 Ext		9. API NUMBER: 43047323910000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0808 FNL 2286 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 23 Township: 10.0S Range: 20.0E Meridian: S		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 11/6/2014	<input type="checkbox"/> ALTER CASING
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS
	<input type="checkbox"/> CHANGE WELL STATUS
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS
	<input type="checkbox"/> DEEPEN
	<input type="checkbox"/> FRACTURE TREAT
	<input checked="" type="checkbox"/> PLUG AND ABANDON
	<input type="checkbox"/> RECLAMATION OF WELL SITE
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> SI TA STATUS EXTENSION
	<input type="checkbox"/> WATER SHUTOFF
	<input checked="" type="checkbox"/> OTHER
	<input type="checkbox"/> WILDCAT WELL DETERMINATION
	OTHER: <input style="width: 100px;" type="text" value="Weld P&A Marker"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

11/06/2014: XTO Energy Inc. has welded P&A marker onto casing. GPS re-verification was made: 39.93818 and -109.63042

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 February 09, 2015

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 303-397-3736	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 1/27/2015	